

ESTIMATION DPR							
State	Odisha	District	Nayagarh	Block	Odagaon	Gram Panchayat	Rabera

Work Code	OD/367/3529/275510/406589/00049598 (Repair & Maintenance of Gothabana P.S, Rabara)
Project Category	Building

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Odagaon	Proposal Date	-
Date of Commencement	13-09-2025	Date of Completion	03-02-2026
Scheme Name	Asset Management School and Mass Education Department	Scheme Component Name	Self/Personal Deposit
Project Sub-Category	Elementary School	Project Type	Repair and Maintenance
Name of Executant	Sradhanjali Sathua Mohapatra		

Administrative Approval Details

Approval No.	OD/367/3529/275510/406589/00049598/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/367/3529/275510/406589/00049598/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	65000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Plastering (AR1014) ::16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	3.825	Sqm
i)	BRM340 : Cement	0.043	0.164475	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	0.06885	1 Cum
2	Flooring (AR0816) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	0.9	Sqm
i)	BRMMR0027 : Wax Polish	1	0.9	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	0.9	1 Sqm.
iii)	BRM340 : Cement	0.2737	0.24633	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.0117	1 Cum

3	<p>Flooring (AR0817b) :.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	4.075	Sqm
i)	<p>BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753</p>	1	4.075	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	0.5603125	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.061125	1 Cum
4	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	0.93025	Cum
i)	<p>BRM029 : Sand for filling and road blinding</p>	1	0.93025	1 Cum

5	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	0.93025	Cum
i)	BRM340 : Cement	2.29	2.1302725	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	0.44652	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	0.89304	1 Cum.
6	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	0.6976875	Cum
i)	BRM340 : Cement	3.23	2.253530625	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.313959375	1 Cum

iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	0.62791875	1 Cum.
7	Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	3.6	Sqm
i)	BRM340 : Cement	0.0372	0.13392	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.027	1 Cum
8	Painting(AR0918Ai) :.Finishing wall one coat with weather coat - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	20.3064	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.075	1.52298	1 Ltr

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM340	5.488840625	1 Qntl.	587.627	3225.3909499469
2	BRM028	0.929154375	1 Cum	716.59	665.82273358125
3	BRMMR0027	0.9	1 Sqm	8.5	7.65
4	BRM130	0.9	1 Sqm.	453.9311111	408.53799999
5	BRM129	4.075	1 Sqm.	414.6011111	1689.4995277325
6	BRM029	0.93025	1 Cum	332.58	309.382545
7	BRM044	0.89304	1 Cum.	1230.01	1098.4481304

8	BRM056	0.62791875	1 Cum.	1672.63	1050.2757388125
9	BRM255	1.52298	1 Ltr	195.03787	297.0387752526
					Total: 8752.0464007157