

ESTIMATION DPR							
State	Odisha	District	Ganjam	Block	Bhanjanagar	Gram Panchayat	Lalsingi

Work Code	OD/354/3367/117649/410674/00050483 (OPEN SPACE DEVELOPMENT WITH OPEN YOGA CENTRE AT LANDAISAH)
Project Category	Other Infrastructure

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Bhanjanagar	Proposal Date	22-12-2023
Date of Commencement	31-10-2025	Date of Completion	-
Scheme Name	Infrastructure Development Fund	Scheme Component Name	Self/Personal Deposit
Project Sub-Category	Rural Park	Project Type	New Work
Name of Executant	MADHU BEHERA		

Administrative Approval Details

Approval No.	OD/354/3367/117649/410674/00050483/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3367/117649/410674/00050483/TS
Fund Sanction No.	16355
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	19.27125	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	20.77407	Cum
i)	BRM029 : Sand for filling and road blinding	1	20.77407	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.48422	Cum
i)	BRM340 : Cement	2.29	12.5588638	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	2.6324256	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	5.2648512	1 Cum.

4	Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	13.7598	Sqm
i)	BRM340 : Cement	0.0372	0.51186456	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.1031985	1 Cum
5	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp. and as per direction of Engineer-in-charge.	-	35.148	Sqm
i)	BRM340 : Cement	0.0358	1.2582984	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.52722	1 Cum

6	<p>Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	3.291	Sqm
i)	<p>BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)</p>	1	3.291	1 Sqm.
ii)	<p>BRMMR0027 : Wax Polish</p>	1	3.291	1 Sqm
iii)	<p>BRM340 : Cement</p>	0.1375	0.4525125	1 Qntl.
iv)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.049365	1 Cum

7	R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	12.929197	Cum
i)	BRM340 : Cement	3.4733	44.9069799401	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	5.81813865	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	4.65451092	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	6.98176638	1 Cum.

8	<p>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	5.63091	Cum
i)	<p>BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %</p>	400	2252.364	1000 Nos
ii)	<p>BRM340 : Cement</p>	0.672	3.78397152	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.28	1.5766548	1 Cum
9	<p>Masonry Brick Work (AR0603ci) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	5.520636	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	5.520636	1 Cum
ii)	BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %	400	2208.2544	1000 Nos
iii)	BRM340 : Cement	0.672	3.709867392	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.54577808	1 Cum
10	Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	29.8372	Sqm
i)	BRM174 : White Cement.	0.0076	0.22676272	1Qntl
ii)	BRM340 : Cement	0.1074	3.20451528	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.6265812	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm conforming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	29.8372	1 Sqm.

11	Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	98.3372	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	8.2603248	1 Ltr
12	Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	63.1872	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	7.8984	1 Litre
13	Painting(AR0901ci) :.Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface) - Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	35.15	Sqm
i)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	2.9526	1 Ltr

14	Painting(AR0903i) :.Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	68.229	Sqm
i)	BRM141 : Enamel paint	0.125	8.528625	1 Litre
15	Plastering (AR1014i) :.16mm thick cement Plaster in CM (1:6) over brick work in outside (outside) - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	33.3488	Sqm
i)	BRM340 : Cement	0.043	1.4339984	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	0.6002784	1 Cum
16	Painting(AR0918ca) :.Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	35.15	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	4.39375	1 Ltr
ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	2.9526	1 Ltr

17	Iron Work(AR1704) :Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	8.6887512	Qntl
i)	BRM341 : Steel	1	8.6887512	1 Qntl.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	20.77407	1 Cum	351.89	7310.1874923
2	BRM340	71.8208717921	1 Qntl.	593.017	42590.997927536
3	BRM028	13.47964023	1 Cum	355.26	4788.7769881098
4	BRM044	5.2648512	1 Cum.	1401.46	7378.478362752
5	BRM131	33.1282	1 Sqm.	660.6811111	21887.175984743
6	BRMMR0027	3.291	1 Sqm	8.5	27.9735
7	BRM060	4.65451092	1 Cum.	1813.98	8443.1897186616
8	BRM052	6.98176638	1 Cum.	1788.5	12486.88917063
9	BRM006	4460.6184	1000 Nos	5.36398	23926.667885232
10	BRMMR0025	5.520636	1 Cum	33	182.180988
11	BRM174	0.22676272	1Qntl	2041.967	463.04199107024
12	BRM253	8.2603248	1 Ltr	159.27787	1315.6869396522
13	BRM140	7.8984	1 Litre	249.58787	1971.344832408
14	BRM252	5.9052	1 Ltr	125.74787	742.566321924
15	BRM141	8.528625	1 Litre	205.58787	1753.3818477788
16	BRM255	4.39375	1 Ltr	195.03787	856.9476413125
17	BRM341	8.6887512	1 Qntl.	6674.467	57992.78315561
Total: 194118.27074772					