

ESTIMATION DPR							
State	Odisha	District	Balasore	Block	Oupada	Gram Panchayat	Shyamasund arpur

Work Code	OD/346/3306/116264/393202/00052045 (Construction of CC road from karunakar Parida house to Pradeep Behera house)
Project Category	Road

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Oupada	Proposal Date	03-12-2022
Date of Commencement	15-09-2025	Date of Completion	16-09-2025
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Jyotirashmi Nayak		

Administrative Approval Details

Approval No.	OD/346/3306/116264/393202/00052045/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/346/3306/116264/393202/00052045/TS
Fund Sanction No.	4897
Fund Sanction Amount (in Rs.)	100000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	0.9301644	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.118621	Cum
i)	BRM029 : Sand for filling and road blinding	1	5.118621	1 Cum
3	Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.129619	Cum
i)	BRM340 : Cement	2.29	16.32682751	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	3.42221712	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	6.84443424	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	5.6034	Cum
i)	BRM340 : Cement	3.23	18.098982	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.52153	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	5.04306	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	14.71536	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0392900112	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	1.85413536	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	5.118621	1 Cum	952.25	4874.20684725
2	BRM340	34.42580951	1 Qntl.	546.307	18807.06071598
3	BRM028	5.94374712	1 Cum	957.19	5689.2953057928
4	BRM045	6.84443424	1 Cum.	1336.79	9149.5712476896
5	BRM056	5.04306	1 Cum.	1946.05	9814.046913
6	BRM104	0.0392900112	1Cum.	58573.086	2301.3372049586
7	BRM092	1.85413536	1Mtr.	229.106	424.79353578816
					Total: 51060.311770459