

ESTIMATION DPR							
State	Odisha	District	Ganjam	Block	Kabisuryanagar	Gram Panchayat	Badamahuri

Work Code	OD/354/3376/117809/412166/00052346 (Completion of incomplete paver road at Loharadhepa)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Kabisuryanagar	Proposal Date	-
Date of Commencement	16-09-2025	Date of Completion	04-10-2025
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant	PRAMOD KUMAR PADHI		

Administrative Approval Details

Approval No.	OD/354/3376/117809/412166/00052346/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3376/117809/412166/00052346/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	101919

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.55526	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.1585	Cum
i)	BRM029 : Sand for filling and road blinding	1	8.1585	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.072	Cum
i)	BRM340 : Cement	2.29	7.03488	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	1.47456	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	2.94912	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	1.986	Cum
i)	BRM340 : Cement	3.23	6.41478	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.8937	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1.7874	1 Cum.

5	miscellaneous(ARM28 7) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-		81.585	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03		2.44755	1 Cum
ii)	BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1		81.585	1 Sqm

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	10.60605	1 Cum	534.17	5665.4337285
2	BRM340	13.44966	1 Qntl.	598.962	8055.83525292
3	BRM028	2.36826	1 Cum	537.54	1273.0344804
4	BRM044	2.94912	1 Cum.	1336.36	3941.0860032
5	BRM056	1.7874	1 Cum.	1737.73	3106.018602
6	BRMM287	81.585	1 Sqm	608.4	49636.314
Total: 71677.72206702					