

ESTIMATION DPR							
State	Odisha	District	Nabarangpur	Block	Tentulikhunti	Gram Panchayat	Digi

Work Code	OD/366/3521/120557/428016/00052547 (IMPROVEMENT OF ROAD WITH CC/GR II METALLING AT BANGRI NALO TO SALPA)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Tentulikhunti	Proposal Date	07-08-2024
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	Mettalling Road	Project Type	Repair and Maintenance
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	OD/366/3521/120557/428016/00052547/TS
Fund Sanction No.	5708
Fund Sanction Amount (in Rs.)	300000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	26.28	Cum
i)	BRM029 : Sand for filling and road blinding	1	26.28	1 Cum

2	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	26.28	Cum
i)	BRM340 : Cement	2.29	60.1812	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	12.6144	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	25.2288	1 Cum.
3	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	21.024	Cum
i)	BRM340 : Cement	3.23	67.90752	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	9.4608	1 Cum

iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	18.9216	1 Cum.
4	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	3.285	Cum

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	26.28	1 Cum	413.05	10854.954
2	BRM340	128.08872	1 Qntl.	579.172	74185.40013984
3	BRM028	22.0752	1 Cum	417.24	9210.656448
4	BRM044	25.2288	1 Cum.	1336.36	33714.759168
5	BRM056	18.9216	1 Cum.	1737.73	32880.631968
Total: 160846.40172384					