

## ESTIMATION DPR

|              |        |                 |          |              |        |                       |          |
|--------------|--------|-----------------|----------|--------------|--------|-----------------------|----------|
| <b>State</b> | Odisha | <b>District</b> | Gajapati | <b>Block</b> | Mohona | <b>Gram Panchayat</b> | Liliguda |
|--------------|--------|-----------------|----------|--------------|--------|-----------------------|----------|

|                         |   |
|-------------------------|---|
| <b>Work Code</b>        | OD/353/3360/275039/413802/00052763 (Maintainence and Improvement of Road with CC / Grade-2 meatling from Kamiliguda to Badakhani) |
| <b>Project Category</b> | Road  |

|                             |                          |                              |  |
|-----------------------------|--------------------------|------------------------------|--|
| <b>Financial Year</b>       | 2024-25                  | <b>Execution Level</b>       | PS   |
| <b>Executing Agency</b>     | Panchayat Samiti, Mohona | <b>Proposal Date</b>         | 31-12-2024   |
| <b>Date of Commencement</b> | 03-02-2026               | <b>Date of Completion</b>    | -  |
| <b>Scheme Name</b>          | 5th SFC Grant in Aid     | <b>Scheme Component Name</b> | Maintenance and improvement of Road infrastructure |
| <b>Project Sub-Category</b> | CC Road                  | <b>Project Type</b>          | New Work   |
| <b>Name of Executant</b>    | Pradeepta Kumar Sethi    |                              |  |

## Administrative Approval Details

|                     |                                       |
|---------------------|---------------------------------------|
| <b>Approval No.</b> | OD/353/3360/275039/413802/00052763/AS |
|---------------------|---------------------------------------|

## Technical Sanction Details

|                                      |                                       |
|--------------------------------------|---------------------------------------|
| <b>Technical Sanction No.</b>        | OD/353/3360/275039/413802/00052763/TS |
| <b>Fund Sanction No.</b>             | 31142                                 |
| <b>Fund Sanction Amount (in Rs.)</b> | 800000                                |

## MATERIAL STATEMENT

| Sl.No. | Activity Name/Material | Qty/unit (B=Analysis Basic Qty/Header Unit) | Quantity (Meaurement Qty) | Unit |
|--------|------------------------|---|---------------------------|------|
|--------|------------------------|---|---------------------------|------|

|      |  |   |       |      |
|------|--|---|-------|------|
| 1    | <p><b>Special items for irrigation works(AR0216)</b><br/> <b>.Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum within an initial lead of 1km from the place of excavation. -</b><br/> Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete.<br/> Per 1 cum.</p> | - | 11700 | Cum  |
| i)   | <b>BRMMR0065</b> : Add for trimming of slope and bed manually.   | 1 | 11700 | L.S. |
| ii)  | <b>BRMMR0102</b> : Cost of mechanical excavation per cum without supervision charge for item AR0216  | 1 | 11700 | Cum  |
| iii) | <b>BRMMR0104</b> : ost of transportation of loose earth within the initial lead of 1 km, excluding supervision charges - AR0216  | 1 | 11700 | Cum  |

| SI.No. | Material Name    | Qty   | Unit | Rate  | Amount |
|--------|------------------|-------|------|-------|--------|
| 1      | <b>BRMMR0065</b> | 11700 | L.S. | 1     | 11700  |
| 2      | <b>BRMMR0102</b> | 11700 | Cum  | 25.01 | 292617 |
| 3      | <b>BRMMR0104</b> | 11700 | Cum  | 40.49 | 473733 |

**Total: 778050**