

ESTIMATION DPR							
State	Odisha	District	Balasure	Block	Oupada	Gram Panchayat	Gadasahi

Work Code	OD/346/3306/116260/393330/00055182 (Repair and Restoration of road from Lambu Kuanar house to paschima Chhak)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Oupada	Proposal Date	-
Date of Commencement	24-09-2025	Date of Completion	24-11-2025
Scheme Name	Severe Cyclonic Storm DANA 2024	Scheme Component Name	Self/Personal Deposit
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant	Gayadhara Singh		

Administrative Approval Details

Approval No.	OD/346/3306/116260/393330/00055182/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/346/3306/116260/393330/00055182/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	150000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.4598155121	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.5386169392	Cum
i)	BRM029 : Sand for filling and road blinding	1	7.5386169392	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.448151685	Cum
i)	BRM340 : Cement	2.29	21.63626735865	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.5351128088	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	9.0702256176	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	8.21832	Cum
i)	BRM340 : Cement	3.23	26.5451736	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.698244	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	7.396488	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	22.09327362	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0589890405654	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	2.78375247612	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	7.5386169392	1 Cum	1191.45	8981.8851522098
2	BRM340	48.18144095865	1 Qntl.	546.307	26321.858465797
3	BRM028	8.2333568088	1 Cum	1196.39	9850.3057524802
4	BRM044	9.0702256176	1 Cum.	1700.92	15427.728157488
5	BRM056	7.396488	1 Cum.	2102.29	15549.56275752
6	BRM104	0.0589890405654	1Cum.	58573.086	3455.1701460947
7	BRM092	2.78375247612	1Mtr.	229.106	637.77439479395
					Total: 80224.284826384