

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Sambalpur	<b>Block</b>	Rairakhol	<b>Gram Panchayat</b>	Luhapank

<b>Work Code</b>	OD/371/3565/121406/382416/00055790 (Construction of Market Complex, Luhapank )
<b>Project Category</b>	Building

<b>Financial Year</b>	2022-23	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Rairakhol	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	14-11-2025	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Creation of Capital Asset for Revenue Generation
<b>Project Sub-Category</b>	Market Complex	<b>Project Type</b>	New Work
<b>Name of Executant</b>	Hemangini Bhoi		

### Administrative Approval Details

<b>Approval No.</b>	OD/371/3565/121406/382416/00055790/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/371/3565/121406/382416/00055790/TS
<b>Fund Sanction No.</b>	
<b>Fund Sanction Amount (in Rs.)</b>	1000000

### MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>43.9112</b>	Cum

2	<b>Earth Work (AR0115)</b> :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	32.24226	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	32.24226	1 Cum
3	<b>Concrete (AR0303)</b> :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.17292	Cum
i)	<b>BRM340</b> : Cement	2.29	37.0359868	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	7.7630016	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	15.5260032	1 Cum.

4	<p><b>R.C.C. Work (AR0404Aa)</b>  <b>∴ Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b>  Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	3.721	Cum
i)	<b>BRM340</b> : Cement	3.4733	12.9241493	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1.67445	1 Cum
iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.33956	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.00934	1 Cum.
v)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.014902605	1Cum.
vi)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.703269	1Mtr.

5	<p><b>R.C.C. Work (AR0404Ab)</b>  <b>:.Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b>  Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)</p>	-	<b>2.377855</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	8.2590037715	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1.07003475	1 Cum
iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.8560278	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.2840417	1 Cum.
v)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.03174436425	1Cum.
vi)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.63	1.49804865	1Mtr.

6	<b>R.C.C. Work (AR0404Ac)</b> <b>:.Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	<b>4.02292</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	13.972808036	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1.810314	1 Cum
iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.4482512	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.1723768	1 Cum.
v)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	17.779697232	1Mtr
vi)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.16706784468	1Cum.

7	<b>R.C.C. Work (AR0404Ad)</b> <b>:.Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.550775	Cum
i)	<b>BRM340</b> : Cement	3.4733	5.3863068075	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	0.69784875	1 Cum
iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.558279	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.8374185	1 Cum.
v)	<b>BRM094</b> : Non-sal bullahs 125mm. mean dia of any length.	3.7695	5.8456463625	1Mtr.
vi)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.1149643784625	1Cum.

8	<b>R.C.C. Work (AR0404Ag)</b> <b>:.Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	<b>6.23348</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	21.650746084	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	2.805066	1 Cum
iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.2440528	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	3.3660792	1 Cum.
v)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	38.782219168	1Mtr
vi)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.313027911856	1Cum.

9	<p><b>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth</b>  - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	15.424775	Cum
i)	<p><b>BRM006</b> : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm<sup>2</sup> with dimensional tolerance ± 2 %</p>	400	6169.91	1000 Nos
ii)	<p><b>BRM340</b> : Cement</p>	0.672	10.3654488	1 Qntl.
iii)	<p><b>BRM028</b> : Screened and washed sharp sand for mortar</p>	0.28	4.318937	1 Cum
10	<p><b>Masonry Brick Work (AR0603ci) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b>  Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	26.352503	Cum

i)	<b>BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK</b>	1	26.352503	1 Cum
ii)	<b>BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm<sup>2</sup> with dimensional tolerance ± 2 %</b>	400	10541.0012	1000 Nos
iii)	<b>BRM340 : Cement</b>	0.672	17.708882016	1 Qntl.
iv)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.28	7.37870084	1 Cum
11	<b>Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc. comp.and as per direction of Engineer-in-charge.</b>	-	<b>136.272768</b>	Sqm
i)	<b>BRM340 : Cement</b>	0.0358	4.8785650944	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.015	2.04409152	1 Cum
12	<b>Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</b>	-	<b>171.03148</b>	Sqm
i)	<b>BRM340 : Cement</b>	0.043	7.35435364	1 Qntl.

ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	3.07856664	1 Cum
13	<b>Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)</b> - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	<b>92.7878</b>	Sqm
i)	<b>BRM340</b> : Cement	0.0372	3.45170616	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.0075	0.6959085	1 Cum
14	<b>Flooring (AR0802ii) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips</b> - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	<b>65.0485</b>	Sqm
i)	<b>BRM340</b> : Cement	0.0858	5.5811613	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.012	0.780582	1 Cum
iii)	<b>BRM057</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1.4961155	1 Cum.

15	<p><b>Other Building Items. (AR1902) :.cement based wall putty (water based) -</b>  Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&amp;P,etc.complete. and as per the direction of Engineer in Charge.</p>	-	159.19	Sqm
i)	<b>BRMMR0038</b> : Cement based putty	0.8	127.352	kg
16	<p><b>Iron Work(AR1703) :.Iron work wrought and put up in trusses and record racks -</b>  Iron work wrought and put up in trusses and record racks including all cost of labour, material, machinery and T &amp; P required for the work etc. as per direction of Engineer-in-Charge.</p>	-	7.416	Qntl
i)	<b>BRM341</b> : Steel	1	7.416	1 Qntl.
17	<p><b>Roofing (AR1132) :.Supplying, feeting &amp; fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties -</b> Supplying, fitting &amp; fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge</p>	-	41.4656	Sqm
i)	<b>BRM149</b> : G.C.I. Sheet 0.30mm thick	1	41.4656	1 Sqm

18	<b>Painting(AR0901d)</b> :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	291.23	Sqm
i)	<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.084	24.46332	1 Ltr
19	<b>Painting(AR0919)</b> :.Finishing wall One Coat with plastic emulsion paint of approved shades on old work (Inside) - Finishing wall One Coat with plastic emulsion paint of approved shades on old work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	159.19	Sqm
i)	<b>BRM140</b> : Plastic Emulsion paint	0.075	11.93925	1 Litre
20	<b>Painting(AR0918Ai)</b> :.Finishing wall one coat with weather coat - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	132.04	Sqm
i)	<b>BRM255</b> : Weather Coat (I.S.I.)	0.075	9.903	1 Ltr

21	<b>Painting(AR0901b)</b> :.Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	<b>10.602288</b>	Sqm
i)	<b>BRM137</b> : Red oxide Primer	0.054	0.572523552	1 Litre
22	<b>R.C.C. Work (AR0409)</b> :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	<b>18.14</b>	Qntl
i)	<b>BRM162</b> : Binding Wire.	0.8	14.512	1 Kg.
ii)	<b>BRM341</b> : Steel	1.05	19.047	1 Qntl.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	32.24226	1 Cum	476.21	15354.0866346
2	<b>BRM340</b>	148.5691178094	1 Qntl.	574.677	85379.254915353
3	<b>BRM028</b>	34.1175016	1 Cum	548.19	18702.873202104
4	<b>BRM044</b>	15.5260032	1 Cum.	1421.31	22067.263608192
5	<b>BRM060</b>	6.4461708	1 Cum.	1889.98	12183.133888584
6	<b>BRM052</b>	9.6692562	1 Cum.	1853.6	17922.93329232
7	<b>BRM104</b>	0.6417071042485	1Cum.	58573.086	37586.765403958
8	<b>BRM092</b>	2.20131765	1Mtr.	229.106	504.3350815209
9	<b>BRM084</b>	56.5619164	1Mtr	250.166	14149.868378122
10	<b>BRM094</b>	5.8456463625	1Mtr.	240.106	1403.5747655144

11	<b>BRM006</b>	16710.9112	1000 Nos	5.4818	91605.87301616
12	<b>BRMMR0025</b>	26.352503	1 Cum	33	869.632599
13	<b>BRM057</b>	1.4961155	1 Cum.	1551.31	2320.938936305
14	<b>BRMMR0038</b>	127.352	kg	30	3820.56
15	<b>BRM341</b>	26.463	1 Qntl.	6691.807	177085.288641
16	<b>BRM149</b>	41.4656	1 Sqm	318.453602	13204.869679091
17	<b>BRM253</b>	24.46332	1 Ltr	159.39677	3899.3741914764
18	<b>BRM140</b>	11.93925	1 Litre	249.70677	2981.3115537225
19	<b>BRM255</b>	9.903	1 Ltr	195.15677	1932.63749331
20	<b>BRM137</b>	0.572523552	1 Litre	143.06677	81.909095333567
21	<b>BRM162</b>	14.512	1 Kg.	90	1306.08
<b>Total: 524362.56437567</b>					