

ESTIMATION DPR							
State	Odisha	District	Kendrapara	Block	Mahakalapada	Gram Panchayat	Alailo

Work Code	OD/360/3438/119122/397047/00056480 ("Repari of Road from school campus to AWC Alailo")
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Mahakalapada	Proposal Date	-
Date of Commencement	24-10-2025	Date of Completion	03-12-2025
Scheme Name	Severe Cyclonic Storm DANA 2024	Scheme Component Name	Self/Personal Deposit
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant	NRMADA SWAIN		

Administrative Approval Details

Approval No.	OD/360/3438/119122/397047/00056480/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/360/3438/119122/397047/00056480/TS
Fund Sanction No.	8443/24
Fund Sanction Amount (in Rs.)	200000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	2.85	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.7	Cum
i)	BRM029 : Sand for filling and road blinding	1	5.7	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	14.25	Cum
i)	BRM340 : Cement	2.29	32.6325	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	6.84	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	13.68	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	11.4	Cum
i)	BRM340 : Cement	3.23	36.822	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	5.13	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	10.26	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	22.8	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.060876	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	2.8728	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	5.7	1 Cum	548.51	3126.507
2	BRM340	69.4545	1 Qntl.	605.327	42042.6841215
3	BRM028	11.97	1 Cum	738.42	8838.8874
4	BRM044	13.68	1 Cum.	2137.15	29236.212
5	BRM056	10.26	1 Cum.	2580.53	26476.2378
6	BRM104	0.060876	1Cum.	58573.086	3565.695183336
7	BRM092	2.8728	1Mtr.	229.106	658.1757168
					Total: 113944.39922164