

ESTIMATION DPR							
State	Odisha	District	Rayagada	Block	Ramanaguda	Gram Panchayat	Gogupadu

Work Code	OD/370/3556/121239/426735/00061910 (RENOVATION OF TANK AT SULUDI GOGUPADU GP)
Project Category	Water Body

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Ramanaguda	Proposal Date	11-10-2021
Date of Commencement	01-12-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Preservation and Development of Water Bodies
Project Sub-Category	Tank	Project Type	New Work
Name of Executant	BABULAL PALAI		

Administrative Approval Details

Approval No.	OD/370/3556/121239/426735/00061910/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/370/3556/121239/426735/00061910/TS
Fund Sanction No.	20430
Fund Sanction Amount (in Rs.)	663375

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	54.3375	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	18.1125	Cum
i)	BRM029 : Sand for filling and road blinding	1	18.1125	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	105.225	Cum
i)	BRM340 : Cement	2.29	240.96525	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	50.508	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	101.016	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	2.5875	Cum
i)	BRM340 : Cement	3.23	8.357625	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.164375	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	2.32875	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	241.5	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.644805	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	30.429	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	18.1125	1 Cum	413.05	7481.368125
2	BRM340	249.322875	1 Qntl.	600.692	149766.2564295
3	BRM028	51.672375	1 Cum	613.29	31690.15086375
4	BRM044	101.016	1 Cum.	1291.11	130422.76776
5	BRM056	2.32875	1 Cum.	1737.73	4046.7387375
6	BRM104	0.644805	1Cum.	58620.646	37798.88564403
7	BRM092	30.429	1Mtr.	276.666	8418.669714
					Total: 369624.83727378