

ESTIMATION DPR							
State	Odisha	District	Jajpur	Block	Dharmasala	Gram Panchayat	Abhayapur

Work Code	OD/356/3397/118327/401250/00063481 (CONSTRUCTION OF PAVER ROAD FROM KHETRABASI SAHOO HOUSE TO RAJENDRA BEHERA HOUSE)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Dharmasala	Proposal Date	-
Date of Commencement	05-11-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant	PRITIMAYEE SAMAL		

Administrative Approval Details

Approval No.	OD/356/3397/118327/401250/00063481/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/356/3397/118327/401250/00063481/TS
Fund Sanction No.	10574
Fund Sanction Amount (in Rs.)	500000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	11.12	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	68.4575	Cum
i)	BRM029 : Sand for filling and road blinding	1	68.4575	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	22.24	Cum
i)	BRM340 : Cement	2.29	50.9296	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	10.6752	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	21.3504	1 Cum.

4	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	150.12	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.4008204	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	18.91512	1Mtr.
5	miscellaneous(ARM28 7) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	437.85	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	13.1355	1 Cum

ii)	BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	437.85	1 Sqm
-----	--	---	--------	-------

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	81.593	1 Cum	413.05	33701.98865
2	BRM340	50.9296	1 Qntl.	577.612	29417.5481152
3	BRM028	10.6752	1 Cum	417.99	4462.126848
4	BRM044	21.3504	1 Cum.	1542.11	32924.665344
5	BRM104	0.4008204	1Cum.	58573.086	23477.287759754
6	BRM092	18.91512	1Mtr.	229.106	4333.56748272
7	BRMM287	437.85	1 Sqm	608.4	266387.94
Total: 394705.12419967					