

ESTIMATION DPR							
State	Odisha	District	Balasore	Block	Baleshwar	Gram Panchayat	Baincha

Work Code	OD/346/3299/275540/392750/00064136 (Construction of CC road from R.D road to Padmalochan Khatua house ., GP: Baincha)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Baleshwar	Proposal Date	25-07-2025
Date of Commencement	02-01-2026	Date of Completion	01-02-2026
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	NIHARIKA MOHAPATRA		

Administrative Approval Details

Approval No.	OD/346/3299/275540/392750/00064136/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/346/3299/275540/392750/00064136/TS
Fund Sanction No.	100000
Fund Sanction Amount (in Rs.)	100000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	2.020120512	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.4171688	Cum
i)	BRM029 : Sand for filling and road blinding	1	8.4171688	1 Cum
3	Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.742245664	Cum
i)	BRM340 : Cement	2.29	20.01974257056	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.19627791872	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	8.39255583744	1 Cum.

4	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	4.6439552	Cum
i)	BRM340 : Cement	3.23	14.999975296	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.08977984	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	4.17955968	1 Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	8.4171688	1 Cum	491.17	4134.260799496
2	BRM340	35.01971786656	1 Qntl.	561.987	19680.626184674
3	BRM028	6.28605775872	1 Cum	496.11	3118.5761146786
4	BRM045	8.39255583744	1 Cum.	1649.27	13841.590566015
5	BRM056	4.17955968	1 Cum.	2258.53	9439.6609240704
Total: 50214.714588934					