

ESTIMATION DPR

State	Odisha	District	Ganjam	Block	Surada	Gram Panchayat	Lathipada
--------------	--------	-----------------	--------	--------------	--------	-----------------------	-----------

Work Code	OD/354/3385/118033/410878/00064211 (Completion of incomplete community centre at Keruajholi)
Project Category	Building

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Surada	Proposal Date	-
Date of Commencement	19-12-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	Community Centre	Project Type	Completion
Name of Executant	Monalisha Panda		

Administrative Approval Details

Approval No.	OD/354/3385/118033/410878/00064211/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3385/118033/410878/00064211/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	100000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	0.54	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	6.52625	Cum
i)	BRM029 : Sand for filling and road blinding	1	6.52625	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	4.3715	Cum
i)	BRM340 : Cement	2.29	10.010735	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	2.09832	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	4.19664	1 Cum.
4	Flooring (AR0802ii) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	20.805	Sqm
i)	BRM340 : Cement	0.0858	1.785069	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.24966	1 Cum
iii)	BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	0.478515	1 Cum.
5	Concrete (AR0307) :Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	1.065	Cum
i)	BRM340 : Cement	3.23	3.43995	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.47925	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	0.9585	1 Cum.

6	<p>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	0.864	Cum
i)	<p>BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %</p>	400	345.6	1000 Nos
ii)	<p>BRM340 : Cement</p>	0.672	0.580608	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.28	0.24192	1 Cum
7	<p>Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	62.9565	Sqm
i)	<p>BRM340 : Cement</p>	0.043	2.7071295	1 Qntl.
ii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.018	1.133217	1 Cum

8	Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-		124.656	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084		10.471104	1 Ltr
9	Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-		80.316	Sqm
i)	BRM142 : Distemper	0.25		20.079	1 Kg.
10	Painting(AR0918Ai) :.Finishing wall one coat with weather coat - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-		66.72	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.075		5.004	1 Ltr

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	6.52625	1 Cum	403.97	2636.4092125
2	BRM340	18.5234915	1 Qntl.	598.442	11085.235300243
3	BRM028	4.202367	1 Cum	407.34	1711.79217378
4	BRM044	4.19664	1 Cum.	1336.36	5608.2218304

5	BRM057	0.478515	1 Cum.	1411.11	675.23730165
6	BRM056	0.9585	1 Cum.	1737.73	1665.614205
7	BRM006	345.6	1000 Nos	5.36398	1853.791488
8	BRM253	10.471104	1 Ltr	159.33732	1668.4376488013
9	BRM142	20.079	1 Kg.	70.40732	1413.70857828
10	BRM255	5.004	1 Ltr	195.09732	976.26698928
Total: 29294.714727934					