

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Nayagarh	<b>Block</b>	Odagaon	<b>Gram Panchayat</b>	Giridipalli

<b>Work Code</b>	OD/367/3529/120706/406491/00064283 (REPAIR & MAINTENANCE OF GOVT. P.S , DAHANGI)
<b>Project Category</b>	Building

<b>Financial Year</b>	2024-25	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Odagaon	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	13-11-2025	<b>Date of Completion</b>	03-12-2025
<b>Scheme Name</b>	Asset Management School and Mass Education Department	<b>Scheme Component Name</b>	Self/Personal Deposit
<b>Project Sub-Category</b>	Elementary School	<b>Project Type</b>	Repair and Maintenance
<b>Name of Executant</b>	Keshab Chandra Beherdalai		

### Administrative Approval Details

<b>Approval No.</b>	OD/367/3529/120706/406491/00064283/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/367/3529/120706/406491/00064283/TS
<b>Fund Sanction No.</b>	
<b>Fund Sanction Amount (in Rs.)</b>	150000

### MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0115)</b> :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	1.33375	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	1.33375	1 Cum

2	<p><b>Concrete (AR0303)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	<b>1.33375</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	3.0542875	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	0.6402	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1.2804	1 Cum.
3	<p><b>Concrete (AR0307)</b>  <b>:.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	<b>1.3918125</b>	Cum
i)	<b>BRM340</b> : Cement	3.23	4.495554375	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	0.626315625	1 Cum

iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1.25263125	1 Cum.
4	<b>R.C.C. Work (AR0404Ag)</b> :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	<b>0.2278125</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	0.79126115625	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	0.102515625	1 Cum
iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.0820125	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.12301875	1 Cum.

v)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	1.41735825	1Mtr
vi)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.011440105875	1Cum.
5	<b>R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	<b>0.2</b>	Qntl
i)	<b>BRM162</b> : Binding Wire.	0.8	0.16	1 Kg.
ii)	<b>BRM341</b> : Steel	1.05	0.21	1 Qntl.
6	<b>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	<b>2.368125</b>	Cum

i)	<b>BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK</b>	1	2.368125	1 Cum
ii)	<b>BRM340 : Cement</b>	0.672	1.59138	1 Qntl.
iii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.28	0.663075	1 Cum
iv)	<b>BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance <math>\pm</math> 2 %</b>	350	828.84375	1000 Nos
7	<b>Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc. comp.and as per direction of Engineer-in-charge.</b>	-	<b>39.01</b>	Sqm
i)	<b>BRM340 : Cement</b>	0.0358	1.396558	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.015	0.58515	1 Cum

8	<p><b>Flooring (AR0816)</b>  <b>:.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor -</b> Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	5.22	Sqm
i)	<b>BRMMR0027</b> : Wax Polish	1	5.22	1 Sqm
ii)	<b>BRM130</b> : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	5.22	1 Sqm.
iii)	<b>BRM340</b> : Cement	0.2737	1.428714	1 Qntl.
iv)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.013	0.06786	1 Cum

9	<p><b>Flooring (AR0817b)</b>  <b>:.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</b></p>	-	28.2	Sqm
i)	<p><b>BRM129</b> : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753</p>	1	28.2	1 Sqm.
ii)	<p><b>BRM340</b> : Cement</p>	0.1375	3.8775	1 Qntl.
iii)	<p><b>BRM028</b> : Screened and washed sharp sand for mortar</p>	0.015	0.423	1 Cum
10	<p><b>Painting(AR0918cb)</b>  <b>:.Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)</b></p>	-	39.01	Sqm
i)	<p><b>BRM255</b> : Weather Coat (I.S.I.)</p>	0.125	4.87625	1 Ltr

ii)	<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	3.5234838709677	1 Ltr
11	<b>Dismantling (AR1612)</b> :.Dismantling and removing 2.5 cm. thick artificial stone flooring - Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	5.307	Sqm
12	<b>Dismantling (AR1613)</b> :.Removing old lime or cement plaster - Removing old lime or cement plaster from walls including raking out joints 12 mm deep and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	54	Sqm
13	<b>Painting(AR0903b)</b> :.Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	11.1375	Sqm
i)	<b>BRM137</b> : Red oxide Primer	0.054	0.601425	1 Litre
ii)	<b>BRM141</b> : Enamel paint	0.125	1.3921875	1 Litre

14	<b>Iron Work(AR1704)</b> :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	1.7325	Qntl
i)	<b>BRM341 : Steel</b>	1	1.7325	1 Qntl.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	1.33375	1 Cum	332.58	443.578575
2	<b>BRM340</b>	16.63525503125	1 Qntl.	587.627	9775.3250082483
3	<b>BRM028</b>	3.10811625	1 Cum	729.61	2267.7126971625
4	<b>BRM044</b>	1.2804	1 Cum.	1230.01	1574.904804
5	<b>BRM056</b>	1.25263125	1 Cum.	1672.63	2095.1886076875
6	<b>BRM060</b>	0.0820125	1 Cum.	2085.28	171.019026
7	<b>BRM052</b>	0.12301875	1 Cum.	2026.9	249.346704375
8	<b>BRM084</b>	1.41735825	1Mtr	250.166	354.5748439695
9	<b>BRM104</b>	0.011440105875	1Cum.	58573.086	670.08230526548
10	<b>BRM162</b>	0.16	1 Kg.	90.1	14.416
11	<b>BRM341</b>	1.9425	1 Qntl.	6666.717	12950.0977725
12	<b>BRMMR0025</b>	2.368125	1 Cum	33	78.148125
13	<b>BRM005</b>	828.84375	1000 Nos	6.00665	4978.5743109375
14	<b>BRMMR0027</b>	5.22	1 Sqm	8.5	44.37
15	<b>BRM130</b>	5.22	1 Sqm.	453.9311111	2369.520399942
16	<b>BRM129</b>	28.2	1 Sqm.	414.6011111	11691.75133302
17	<b>BRM255</b>	4.87625	1 Ltr	195.03787	951.0534135875
18	<b>BRM253</b>	3.5234838709677	1 Ltr	159.27787	561.2130059471
19	<b>BRM137</b>	0.601425	1 Litre	142.94787	85.97242271475
20	<b>BRM141</b>	1.3921875	1 Litre	199.22787	277.36255026562
<b>Total: 51604.211905623</b>					