

ESTIMATION DPR							
State	Odisha	District	Balangir	Block	Gudvella	Gram Panchayat	Chinched

Work Code	OD/345/3289/115869/420441/00065274 (Renovation of Lakharpadar Bhangamunda Tank)
Project Category	Water Body

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Gudvella	Proposal Date	-
Date of Commencement	03-12-2025	Date of Completion	04-12-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Tank	Project Type	Renovation or Rejuvenation
Name of Executant	SUSHANTA KUMAR BARIK		

Administrative Approval Details

Approval No.	OD/345/3289/115869/420441/00065274/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/345/3289/115869/420441/00065274/TS
Fund Sanction No.	1641
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	61.94982	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	42.922125	Cum
i)	BRM029 : Sand for filling and road blinding	1	42.922125	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	72.8181575	Cum
i)	BRM340 : Cement	2.29	166.753580675	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	34.9527156	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	69.9054312	1 Cum.

4	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	16.98	Sqm
i)	BRM340 : Cement	0.0358	0.607884	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.2547	1 Cum
5	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	111.9545	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.298918515	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	14.106267	1Mtr.

6	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	17.1039375	Cum
i)	BRM340 : Cement	3.23	55.245718125	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	7.696771875	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	15.39354375	1 Cum.
7	<p>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	2.407725	Cum

i)	BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance \pm 2 %	400	963.09	1000 Nos
ii)	BRM340 : Cement	0.672	1.6179912	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	0.674163	1 Cum
8	Special items for irrigation works(AR0216) :.Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum within an initial lead of 1km from the place of excavation. - Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete. Per 1 cum.	-	6056.97825	Cum
i)	BRMMR0065 : Add for trimming of slope and bed manually.	1	6056.97825	L.S.
ii)	BRMMR0102 : Cost of mechanical excavation per cum without supervision charge for item AR0216	1	6056.97825	Cum

iii)	BRMMR0104 : ost of transportation of loose earth within the initial lead of 1 km, excluding supervision charges - AR0216	1	6056.97825	Cum
------	---	---	------------	-----

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	42.922125	1 Cum	413.05	17728.98373125
2	BRM340	224.225174	1 Qntl.	534.912	119940.73627469
3	BRM028	43.578350475	1 Cum	417.99	18215.314715045
4	BRM044	69.9054312	1 Cum.	1596.76	111622.19632291
5	BRM104	0.298918515	1Cum.	58573.086	17508.579886087
6	BRM092	14.106267	1Mtr.	229.106	3231.830407302
7	BRM056	15.39354375	1 Cum.	1998.13	30758.301573187
8	BRM006	963.09	1000 Nos	5.59962	5392.9380258
9	BRMMR0065	6056.97825	L.S.	1	6056.97825
10	BRMMR0102	6056.97825	Cum	25.01	151485.0260325
11	BRMMR0104	6056.97825	Cum	40.49	245247.0493425
Total: 727187.93456127					