

ESTIMATION DPR

State	Odisha	District	Gajapati	Block	Kasinagar	Gram Panchayat	Budura
--------------	--------	-----------------	----------	--------------	-----------	-----------------------	--------

Work Code	OD/353/3359/117478/414508/00065581 (Construction of drain from Telega Sahiending to Saibaba temple at Vanna)
Project Category	Road

Financial Year	2020-21	Execution Level	PS
Executing Agency	Panchayat Samiti, Kasinagar	Proposal Date	-
Date of Commencement	27-11-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Ch Uma Sankar Patra		

Administrative Approval Details

Approval No.	OD/353/3359/117478/414508/00065581/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/353/3359/117478/414508/00065581/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	101920

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	15.75	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	2.25	Cum
i)	BRM029 : Sand for filling and road blinding	1	2.25	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.25	Cum
i)	BRM340 : Cement	2.29	18.8925	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	3.96	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	7.92	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	2.205	Cum
i)	BRM340 : Cement	3.23	7.12215	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.99225	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1.9845	1 Cum.
5	<p>R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	1.62	Qntl
i)	BRM162 : Binding Wire.	0.8	1.296	1 Kg.
ii)	BRM341 : Steel	1.05	1.701	1 Qntl.

6	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-		30	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267		0.0801	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126		3.78	1Mtr.
7	R.C.C. Work (AR0410a) :.Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-		10.8	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.6222222222222222		6.72	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222		0.05424	1Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	2.25	1 Cum	413.05	929.3625
2	BRM340	26.01465	1 Qntl.	606.537	15778.84776705
3	BRM028	4.95225	1 Cum	417.99	2069.9909775

4	BRM044	7.92	1 Cum.	1596.76	12646.3392
5	BRM056	1.9845	1 Cum.	1998.13	3965.288985
6	BRM162	1.296	1 Kg.	90.1	116.7696
7	BRM341	1.701	1 Qntl.	6213.497	10569.158397
8	BRM104	0.13434	1Cum.	58573.086	7868.70837324
9	BRM092	3.78	1Mtr.	229.106	866.02068
10	BRM084	6.72	1Mtr	250.166	1681.11552
Total: 56491.60199979					