

ESTIMATION DPR							
State	Odisha	District	Jajpur	Block	Badchana	Gram Panchayat	Barpada

Work Code	OD/356/3394/118243/401812/00065985 (Construction of Maa Sumudei Community Centre)
Project Category	Building

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Badchana	Proposal Date	-
Date of Commencement	23-12-2025	Date of Completion	15-01-2026
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	Community Centre	Project Type	New Work
Name of Executant	Sridhar Barik		

Administrative Approval Details

Approval No.	OD/356/3394/118243/401812/00065985/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/356/3394/118243/401812/00065985/TS
Fund Sanction No.	3139
Fund Sanction Amount (in Rs.)	200000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	15.7464	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	13.82256	Cum
i)	BRM029 : Sand for filling and road blinding	1	13.82256	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.95217	Cum
i)	BRM340 : Cement	2.29	9.0504693	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	1.8970416	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	3.7940832	1 Cum.

4	<p>R.C.C. Work (AR0404Aa) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	2.592	Cum
i)	BRM340 : Cement	3.4733	9.0027936	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.1664	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.93312	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.39968	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.01038096	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.489888	1Mtr.

5	R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	1.23375	Cum
i)	BRM340 : Cement	3.4733	4.285183875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.5551875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.44415	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.666225	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.0164705625	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	0.7772625	1Mtr.

6	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	2.916	Cum
i)	BRM340 : Cement	3.4733	10.1281428	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.3122	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.04976	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.57464	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	12.8875536	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.121098564	1Cum.

7	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	6.01386	Cum
i)	BRM340 : Cement	0.672	4.04131392	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.6838808	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	2104.851	1000 Nos
8	<p>R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	5.96	Qntl
i)	BRM162 : Binding Wire.	0.8	4.768	1 Kg.
ii)	BRM341 : Steel	1.05	6.258	1 Qntl.

9	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	22.701	Sqm
i)	BRM340 : Cement	0.0358	0.8126958	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.340515	1 Cum

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	13.82256	1 Cum	673.45	9308.803032
2	BRM340	37.320599295	1 Qntl.	580.557	21666.735164907
3	BRM028	6.9552249	1 Cum	678.39	4718.355019911
4	BRM044	3.7940832	1 Cum.	1737.41	6591.878092512
5	BRM060	2.42703	1 Cum.	2211.91	5368.3719273
6	BRM052	3.640545	1 Cum.	2179.1	7933.1116095
7	BRM104	0.1479500865	1Cum.	58573.086	8665.8931402719
8	BRM092	1.2671505	1Mtr.	229.106	290.311782453
9	BRM084	12.8875536	1Mtr	250.166	3224.0277338976
10	BRM005	2104.851	1000 Nos	6.1891	13027.1333241
11	BRM162	4.768	1 Kg.	90.1	429.5968
12	BRM341	6.258	1 Qntl.	6229.227	38982.502566
Total: 120206.72019285					