

ESTIMATION DPR							
State	Odisha	District	Jajpur	Block	Sukinda	Gram Panchayat	Sarangapur

Work Code	OD/356/3403/118513/400565/00067170 (Renovation of Brahman Sahi Pond)
Project Category	Water Body

Financial Year	2020-21	Execution Level	PS
Executing Agency	Panchayat Samiti, Sukinda	Proposal Date	-
Date of Commencement	10-12-2025	Date of Completion	06-01-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Pathway	Project Type	Renovation or Rejuvenation
Name of Executant	Hiranya Laxmi Nayak		

Administrative Approval Details

Approval No.	OD/356/3403/118513/400565/00067170/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/356/3403/118513/400565/00067170/TS
Fund Sanction No.	8050
Fund Sanction Amount (in Rs.)	500000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	21.42	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	44.625	Cum
i)	BRM029 : Sand for filling and road blinding	1	44.625	1 Cum
3	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	180.88	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.4829496	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	22.79088	1Mtr.

4	<p>miscellaneous(ARM28 7) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	374.85	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	11.2455	1 Cum
ii)	BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	374.85	1 Sqm

5	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	27.132	Cum
i)	BRM340 : Cement	2.29	62.13228	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	13.02336	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	26.04672	1 Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	55.8705	1 Cum	608.35	33988.818675
2	BRM104	0.4829496	1Cum.	58573.086	28287.848454466
3	BRM092	22.79088	1Mtr.	229.106	5221.52735328
4	BRMM287	374.85	1 Sqm	608.4	228058.74
5	BRM340	62.13228	1 Qntl.	580.557	36071.33007996
6	BRM028	13.02336	1 Cum	613.29	7987.0964544
7	BRM044	26.04672	1 Cum.	1607.21	41862.5488512
Total: 381477.90986831					