

ESTIMATION DPR							
State	Odisha	District	Nayagarh	Block	Bhapur	Gram Panchayat	Badasahara

Work Code	OD/367/3523/120588/406161/00069166 (Const. of Gopalprasad Harijana sahi Road Paver block)
Project Category	Other Infrastructure

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Bhapur	Proposal Date	-
Date of Commencement	16-12-2025	Date of Completion	14-01-2026
Scheme Name	Bikashita Gaon Bikashita Odisha	Scheme Component Name	Viksit Gaon Vikshit Odisha (VGVO)
Project Sub-Category	Parking shed	Project Type	New Work
Name of Executant	Dillip Udalin		

Administrative Approval Details

Approval No.	OD/367/3523/120588/406161/00069166/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/367/3523/120588/406161/00069166/TS
Fund Sanction No.	2119
Fund Sanction Amount (in Rs.)	490314

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	10.4388	Cum

i)	BRM340 : Cement	3.23	33.717324	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	4.69746	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	9.39492	1 Cum.
2	miscellaneous(ARM287) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	650.39	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	19.5117	1 Cum
ii)	BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	650.39	1 Sqm

Sl.No.	Material Name	Qty	Unit	Rate	Amount
--------	---------------	-----	------	------	--------

1	BRM340	33.717324	1 Qntl.	587.627	19813.209950148
2	BRM028	4.69746	1 Cum	430.15	2020.612419
3	BRM056	9.39492	1 Cum.	1802.83	16937.4436236
4	BRM029	19.5117	1 Cum	423.72	8267.497524
5	BRMM287	650.39	1 Sqm	608.4	395697.276
					Total: 442736.03951675