

ESTIMATION DPR							
State	Odisha	District	Jagatsinghpur	Block	Balikuda	Gram Panchayat	Krushnadaspur

Work Code	OD/355/3386/118057/398239/00070065 (Construction of CC Road from RD Road to GP Office)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Balikuda	Proposal Date	-
Date of Commencement	08-01-2026	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	SAGARIKA ROUT		

Administrative Approval Details

Approval No.	OD/355/3386/118057/398239/00070065/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/355/3386/118057/398239/00070065/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	119875

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0101aa) ∴.Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift - Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum	-	1.725	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.75	Cum
i)	BRM029 : Sand for filling and road blinding	1	5.75	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.775	Cum
i)	BRM340 : Cement	2.29	22.38475	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.692	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	9.384	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	5.175	Cum
i)	BRM340 : Cement	3.23	16.71525	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.32875	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	4.6575	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	12.65	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0337755	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	1.5939	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	5.75	1 Cum	638.67	3672.3525
2	BRM340	39.1	1 Qntl.	603.877	23611.5907
3	BRM028	7.02075	1 Cum	647.18	4543.688985
4	BRM044	9.384	1 Cum.	2445.96	22952.88864
5	BRM056	4.6575	1 Cum.	2847.33	13261.439475
6	BRM104	0.0337755	1Cum.	58573.086	1978.335266193
7	BRM092	1.5939	1Mtr.	229.106	365.1720534
					Total: 70385.467619593