

ESTIMATION DPR							
State	Odisha	District	Kandhamal	Block	Tumudibandh	Gram Panchayat	Mundigarh

Work Code	OD/359/3433/119016/416941/00072282 (Improvement of Rural Haat at Mundigada)
Project Category	Building

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Tumudibandh	Proposal Date	31-05-2022
Date of Commencement	21-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Development of Rural Haat
Project Sub-Category	Market Complex	Project Type	New Work
Name of Executant	Sunil		

Administrative Approval Details

Approval No.	OD/359/3433/119016/416941/00072282/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/359/3433/119016/416941/00072282/TS
Fund Sanction No.	22570
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	56.598204	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	38.672915636883	Cum
i)	BRM029 : Sand for filling and road blinding	1	38.672915636883	1 Cum
3	Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.112288253037	Cum
i)	BRM340 : Cement	2.29	36.897140099455	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	7.7338983614578	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	15.467796722916	1 Cum.

4	Masonry Stone Work (AR0703) :.Random rubble H.G. stone of masonry. - Random rubble H.G. stone of size not less than 0.0025 cum stacked masonry in cement mortar (1:6) in foundation and plinth including watering, curing for seven days with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	24.582432858714	Cum
i)	BRM340 : Cement	0.8151	20.037141023138	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.34	8.3580271719628	1 Cum
iii)	BRM034 : Granite broken stone of size not less than 0.0025 Cum. Stacked	1	24.582432858714	1 Cum.
5	R.C.C. Work (AR0404Aa) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	11.32672	Cum
i)	BRM340 : Cement	3.4733	39.341096576	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	5.097024	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	4.0776192	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	6.1164288	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.0453635136	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	2.14075008	1Mtr.
6	R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	3.4340903572608	Cum
i)	BRM340 : Cement	3.4733	11.927626037874	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.5453406607674	1 Cum

iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.2362725286139	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.8544087929208	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.045845106269432	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	2.1634769250743	1Mtr.
7	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	8.5060256724608	Cum
i)	BRM340 : Cement	3.4733	29.543978968158	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.8277115526074	1 Cum

iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	3.0621692420859	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	4.5932538631288	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	37.593231062008	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.35324674015162	1Cum.
8	R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	13.24386930048	Cum
i)	BRM340 : Cement	3.4733	45.999931241357	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	5.959741185216	1 Cum

iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	4.7677929481728	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	7.1516894222592	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	82.398057239866	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.66507003343606	1Cum.
9	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	36.5	Qntl
i)	BRM162 : Binding Wire.	0.8	29.2	1 Kg.
ii)	BRM341 : Steel	1.05	38.325	1 Qntl.

10	<p>Flooring (AR0802i) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.</p>	-	59.0781511166	Sqm
i)	BRM340 : Cement	0.0858	5.0689053658043	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.7089378133992	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1.3587974756818	1 Cum.
11	<p>Masonry Brick Work (AR0603di) :.C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:4) in superstructure - Brickwork with C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	6.1507204448	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	6.1507204448	1 Cum

ii)	BRM001 : Well burnt clamp burnt bricks (25 Cm. x 12Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm2 with dimensional tolerance ± 8 percent.	350	2152.75215568	1000 Nos
iii)	BRM340 : Cement	1	6.1507204448	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.722201724544	1 Cum

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	38.672915636883	1 Cum	411.11	15898.822347479
2	BRM340	194.96653975659	1 Qntl.	608.852	118705.76766388
3	BRM028	34.952882469954	1 Cum	483.09	16885.38799241
4	BRM045	15.467796722916	1 Cum.	1128.47	17454.944567908
5	BRM034	24.582432858714	1 Cum.	698.17	17162.717148968
6	BRM060	13.143853918873	1 Cum.	1889.98	24841.621029591
7	BRM052	19.715780878309	1 Cum.	1853.6	36545.171436033
8	BRM104	1.1095253934571	1Cum.	58620.646	65041.095317861
9	BRM092	4.3042270050743	1Mtr.	276.666	1190.8332685859
10	BRM084	119.99128830187	1Mtr	297.726	35724.526300964
11	BRM162	29.2	1 Kg.	90.1	2630.92
12	BRM341	38.325	1 Qntl.	7109.632	272476.6464
13	BRM056	1.3587974756818	1 Cum.	1933.03	2626.5962844172
14	BRMMR0025	6.1507204448	1 Cum	33	202.9737746784
15	BRM001	2152.75215568	1000 Nos	5.111375	11003.523549739
Total: 638391.54708251					