

ESTIMATION DPR							
State	Odisha	District	Kandhamal	Block	Tumudibandh	Gram Panchayat	Tumudibandh

Work Code	OD/359/3433/119018/416964/00072307 (Construction of GP Godown at Tumudibandha)
Project Category	Building

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Tumudibandh	Proposal Date	24-08-2021
Date of Commencement	21-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Godown	Project Type	New Work
Name of Executant	Sunil		

Administrative Approval Details

Approval No.	OD/359/3433/119018/416964/00072307/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/359/3433/119018/416964/00072307/TS
Fund Sanction No.	14
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	32.9926116	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	25.11770952	Cum
i)	BRM029 : Sand for filling and road blinding	1	25.11770952	1 Cum
3	Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	11.55396232	Cum
i)	BRM340 : Cement	2.29	26.4585737128	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	5.5459019136	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	11.0918038272	1 Cum.

4	Masonry Stone Work (AR0703) :.Random rubble H.G. stone of masonry. - Random rubble H.G. stone of size not less than 0.0025 cum stacked masonry in cement mortar (1:6) in foundation and plinth including watering, curing for seven days with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	13.84978086016	Cum
i)	BRM340 : Cement	0.8151	11.288956379116	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.34	4.7089254924544	1 Cum
iii)	BRM034 : Granite broken stone of size not less than 0.0025 Cum. Stacked	1	13.84978086016	1 Cum.
5	R.C.C. Work (AR0404Aa) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	5.66336	Cum
i)	BRM340 : Cement	3.4733	19.670548288	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.548512	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.0388096	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	3.0582144	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.0226817568	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1.07037504	1Mtr.
6	R.C.C. Work (AR0404Ab) :Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	1.8209798975872	Cum
i)	BRM340 : Cement	3.4733	6.3248094782896	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.81944095391424	1 Cum

iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.65555276313139	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.98332914469709	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.024310081632789	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1.1472173354799	1Mtr.
7	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	4.92022381168	Cum
i)	BRM340 : Cement	3.4733	17.089413365108	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.214100715256	1 Cum

iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.7712805722048	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.6569208583072	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	21.745421158101	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.20433197467526	1Cum.
8	R.C.C. Work (AR0404Ad) :Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.35894022208	Cum
i)	BRM340 : Cement	3.4733	4.7200070733505	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.611523099936	1 Cum

iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.4892184799488	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.7338277199232	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	5.1225251671306	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.10074299495357	1Cum.
9	R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	11.706777442483	Cum
i)	BRM340 : Cement	3.4733	40.661150090976	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	5.2680498491174	1 Cum

iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	4.2144398792939	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	6.3216598189408	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	72.834886536152	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.58788158418466	1Cum.
10	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	25.47	Qntl
i)	BRM162 : Binding Wire.	0.8	20.376	1 Kg.
ii)	BRM341 : Steel	1.05	26.7435	1 Qntl.

11	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	21.54068320544	Cum
i)	<p>BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK</p>	1	21.54068320544	1 Cum
ii)	<p>BRM340 : Cement</p>	0.672	14.475339114056	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.28	6.0313912975232	1 Cum
iv)	<p>BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %</p>	350	7539.239121904	1000 Nos
12	<p>Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	112.846951525	Sqm
i)	<p>BRM340 : Cement</p>	0.0358	4.039920864595	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.692704272875	1 Cum
13	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	106.641031125	Sqm
i)	BRM340 : Cement	0.043	4.585564338375	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.91953856025	1 Cum
14	Plastering (AR1017) :.20mm thick cement Plaster in CM (1:4) over masonry work in inside. - 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	90.2407623417	Sqm
i)	BRM340 : Cement	0.0744	6.7139127182225	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.021	1.8950560091757	1 Cum

15	<p>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	55.7418	Sqm
i)	BRM174 : White Cement.	0.0076	0.42363768	1Qntl
ii)	BRM340 : Cement	0.1074	5.98666932	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	1.1705778	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	55.7418	1 Sqm.

16	<p>Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	5.8064375	Sqm
i)	<p>BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)</p>	1	5.8064375	1 Sqm.
ii)	<p>BRMMR0027 : Wax Polish</p>	1	5.8064375	1 Sqm
iii)	<p>BRM340 : Cement</p>	0.1375	0.79838515625	1 Qntl.
iv)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.0870965625	1 Cum
17	<p>Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.</p>	-	4.29	Qntl
i)	<p>BRM341 : Steel</p>	1	4.29	1 Qntl.

18	Painting(AR0918c) :.Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work (Outside) - Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-		275.22978265	Sqm
i)	BRM143 : Cement paint	0.25		68.8074456625	1 Kg.
ii)	BRM340 : Cement	0.010763440860215		2.9624194885231	1 Qntl.
19	Painting(AR0903a) :.Painting two coats of enamel paint with a coat of wood primer in inner surface paint (Inside) - Painting two coats of enamel paint with a coat of wood primer in inner surface paint including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)	-		28.3063828125	Sqm
i)	BRM141 : Enamel paint	0.125		3.5382978515625	1 Litre
ii)	BRM138 : Wood Primer	0.075		2.1229787109375	1 Litre

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	25.11770952	1 Cum	411.11	10326.141560767
2	BRM340	165.77566938766	1 Qntl.	602.907	99947.311503507
3	BRM028	34.512818526602	1 Cum	483.09	16672.797502016
4	BRM045	11.0918038272	1 Cum.	1128.47	12516.76786488
5	BRM034	13.84978086016	1 Cum.	633.07	8767.8807691415
6	BRM060	9.1693012945789	1 Cum.	1759.78	16135.953032174
7	BRM052	13.753951941868	1 Cum.	1723.4	23703.560776616

8	BRM104	0.93994839224627	1Cum.	58620.646	55100.381960138
9	BRM092	2.2175923754799	1Mtr.	276.666	613.53241215453
10	BRM084	94.580307694253	1Mtr	297.726	28159.016688579
11	BRM094	5.1225251671306	1Mtr.	287.666	1473.5763247278
12	BRM162	20.376	1 Kg.	90.1	1835.8776
13	BRM341	31.0335	1 Qntl.	7103.687	220452.2705145
14	BRMMR0025	21.54068320544	1 Cum	33	710.84254577952
15	BRM005	7539.239121904	1000 Nos	5.9641	44964.776046948
16	BRM174	0.42363768	1Qntl	2041.967	865.05416251656
17	BRM131	61.5482375	1 Sqm.	660.6811111	40663.757937747
18	BRMMR0027	5.8064375	1 Sqm	8.5	49.35471875
19	BRM143	68.8074456625	1 Kg.	48.07787	3308.1154275937
20	BRM141	3.5382978515625	1 Litre	205.58787	727.43111872831
21	BRM138	2.1229787109375	1 Litre	155.32787	329.75776122527
				Total: 587324.15822849	