

ESTIMATION DPR							
State	Odisha	District	Kendujhar	Block	Anandapur	Gram Panchayat	Panasadiha

Work Code	OD/361/3443/119262/386985/00074466 (Rep & Maint of Govt.UPS panasadiha (25-26) asset Management)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Anandapur	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	Asset Management School and Mass Education Department	Scheme Component Name	Self/Personal Deposit
Project Sub-Category	Elementary School	Project Type	Repair and Maintenance
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	150000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.2	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	0.3	Cum
i)	BRM029 : Sand for filling and road blinding	1	0.3	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	0.45	Cum
i)	BRM340 : Cement	2.29	1.0305	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	0.216	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	0.432	1 Cum.

4	<p>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	1.35	Cum
i)	<p>BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %</p>	400	540	1000 Nos
ii)	<p>BRM340 : Cement</p>	0.672	0.9072	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.28	0.378	1 Cum
5	<p>Flooring (AR0817ab) :.Fifth Floor - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	59.975	Sqm

i)	BRM132 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Coloured / Printed series(Homogeneous)	1	59.975	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	59.975	1 Sqm
iii)	CON026 : cement (Other way)	0.1375	8.2465625	1000 kg
iv)	BRM340 : Cement	0.1375	8.2465625	1 Qntl.
v)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.899625	1 Cum

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	0.3	1 Cum	1008.91	302.673
2	BRM340	10.1842625	1 Qntl.	655.912	6679.9799849
3	BRM028	1.493625	1 Cum	1018.91	1521.86944875
4	BRM044	0.432	1 Cum.	2317.16	1001.01312
5	BRM006	540	1000 Nos	6.0709	3278.286
6	BRM132	59.975	1 Sqm.	722.7213901	43345.215371248
7	BRMMR0027	59.975	1 Sqm	8.5	509.7875
8	CON026	8.2465625	1000 kg	0	0
Total: 56638.824424898					