

ESTIMATION DPR							
State	Odisha	District	Sundargarh	Block	Nuagaon	Gram Panchayat	Menmena

Work Code	OD/373/3585/121708/384428/00074680 (Construction of Additional Classroom at Govt. Primary School)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Nuagaon	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	Bikashita Gaon Bikashita Odisha	Scheme Component Name	Viksit Gaon Vikshit Odisha (VGVO)
Project Sub-Category	Elementary School	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	OD/373/3585/121708/384428/00074680/TS
Fund Sanction No.	4514/ZP
Fund Sanction Amount (in Rs.)	700000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	27.2436	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	22.9943	Cum
i)	BRM029 : Sand for filling and road blinding	1	22.9943	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.7203	Cum
i)	BRM340 : Cement	2.29	19.969487	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.185744	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	8.371488	1 Cum.

4	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth</p> <p>- Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	5.2332	Cum
i)	BRM340 : Cement	0.672	3.5167104	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.465296	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1831.62	1000 Nos
5	<p>Masonry Brick Work (AR0603bi) :.First floor</p> <p>- Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	14.40006	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	14.40006	1 Cum

ii)	BRM340 : Cement	0.672	9.67684032	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	4.0320168	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance \pm 2 %	350	5040.021	1000 Nos
6	R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	45.114	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.12045438	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	5.684364	1Mtr.
7	R.C.C. Work (AR0410d) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	42.604	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	23.533638095238	1Mtr

ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.22113504761905	1Cum.
8	R.C.C. Work (AR0410e) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	10.013	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	2.6958076923077	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.053017551282051	1Cum.
9	R.C.C. Work (AR0410a) :.Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	49.8554	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.62222222222222	31.021137777778	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.25038489777778	1Cum.

10	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	14.63	Qntl
i)	BRM162 : Binding Wire.	0.8	11.704	1 Kg.
ii)	BRM341 : Steel	1.05	15.3615	1 Qntl.
11	Concrete (AR0317) :.2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge. (new work)	-	42.4634	Sqm
i)	BRM340 : Cement	0.1208	5.12957872	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0169	0.71763146	1 Cum
iii)	BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	0.71763146	1 Cum.

12	Plastering (AR1004) ::12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	109.56	Sqm
i)	BRM340 : Cement	0.0358	3.922248	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.6434	1 Cum
13	Plastering (AR1014) ::16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	128.0405	Sqm
i)	BRM340 : Cement	0.043	5.5057415	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	2.304729	1 Cum

14	<p>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	31.72	Sqm
i)	BRM174 : White Cement.	0.0076	0.241072	1Qntl
ii)	BRM340 : Cement	0.1074	3.406728	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.66612	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	31.72	1 Sqm.
15	<p>Flooring (AR0817aa) :.First floor - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	7.761	Sqm

i)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	7.761	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	7.761	1 Sqm
iii)	BRM340 : Cement	0.1375	1.0671375	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.116415	1 Cum
16	Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	2.6524	Qntl
i)	BRM341 : Steel	1	2.6524	1 Qntl.

17	<p>R.C.C. Work (AR0404Aa) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	16.24824	Cum
i)	BRM340 : Cement	3.4733	56.435011992	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	7.311708	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	5.8493664	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	8.7740496	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.0650742012	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	3.07091736	1Mtr.

18	Painting(AR0901b) :.Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	15.71	Sqm
i)	BRM137 : Red oxide Primer	0.054	0.84834	1 Litre
19	Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	128.04	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	16.005	1 Litre
20	Painting(AR0918g) :.Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work .(Outside) - Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	109.56	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	13.695	1 Ltr

ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	9.20304	1 Ltr
21	Painting(AR0901c) :.Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	137.6	Sqm
i)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	11.5584	1 Ltr

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	22.9943	1 Cum	517.21	11892.881903
2	BRM340	108.629483432	1 Qntl.	555.297	60321.626261339
3	BRM028	22.44306026	1 Cum	522.15	11718.643914759
4	BRM044	8.371488	1 Cum.	1596.76	13367.25717888
5	BRM005	6871.641	1000 Nos	6.1539	42287.3915499
6	BRMMR0025	14.40006	1 Cum	33	475.20198
7	BRM104	0.71006607787888	1Cum.	58573.086	41590.761445282
8	BRM092	8.75528136	1Mtr.	229.106	2005.8874912642
9	BRM084	54.554775873016	1Mtr	250.166	13647.750061049
10	BRM094	2.6958076923077	1Mtr.	240.106	647.27960176923
11	BRM162	11.704	1 Kg.	90.1	1054.5304
12	BRM341	18.0139	1 Qntl.	6404.617	115372.1301763
13	BRM064	0.71763146	1 Cum.	1451.71	1041.7927667966
14	BRM174	0.241072	1Qntl	2024.787	488.119451664
15	BRM131	39.481	1 Sqm.	668.4376117	26390.585347528
16	BRMMR0027	7.761	1 Sqm	8.5	65.9685
17	BRM060	5.8493664	1 Cum.	1991.51	11649.071679264
18	BRM052	8.7740496	1 Cum.	1983.8	17405.95959648
19	BRM137	0.84834	1 Litre	142.5689	120.946900626
20	BRM140	16.005	1 Litre	249.9089	3999.7919445
21	BRM255	13.695	1 Ltr	195.3589	2675.4401355

22	BRM252	20.76144	1 Ltr	126.0689	2617.371903216
Total: 380836.39018912					