

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Gajapati	<b>Block</b>	Gosani	<b>Gram Panchayat</b>	Kerandi

<b>Work Code</b>	OD/353/3357/117448/414651/00013353 (Completion of incomplete CC road and drain from Simanchala Behera House to Sanju Patro House near Makatotamma Temple of Ramaswamipur of GP Kerandi)
<b>Project Category</b>	Road

<b>Financial Year</b>	2022-23	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Gosani	<b>Proposal Date</b>	08-06-2021
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance and improvement of Road infrastructure
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	Completion
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	1892
<b>Fund Sanction Amount (in Rs.)</b>	22500

### ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<b>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.45	Cum
i)	<b>BRM340 : Cement</b>	2.29	21.6405	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	4.536	1 Cum
iii)	<b>BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)</b>	0.96	9.072	1 Cum.
2	<b>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	63	Sqm
i)	<b>BRM104 : Non Sal wood scantling &amp; plants(Tentera, Kasi, Gamhari, Kuruma)</b>	0.00267	0.16821	1Cum.
ii)	<b>BRM092 : Non-sal bullahs 75mm. mean dia of any length.</b>	0.000614	0.038682	1Mtr.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM028</b>	4.536	1 Cum	319.5	1449.252
2	<b>BRM044</b>	9.072	1 Cum.	419	3801.168

