

ESTIMATION DPR							
State	Odisha	District	Ganjam	Block	Purushottampur	Gram Panchayat	Jamuni

Work Code	OD/354/3381/117937/412229/00017471 (CONST OF CC PAVER ROAD FROM JAGANATH MANDIR TO KUMBARA SAHI ROAD VIA KUMBARA SAHI CHAKA OF JAMUNI)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Purushottampur	Proposal Date	10-12-2024
Date of Commencement	19-05-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant	Parameswari Patra		

Administrative Approval Details

Approval No.	OD/354/3381/117937/412229/00017471/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3381/117937/412229/00017471/TS
Fund Sanction No.	29143
Fund Sanction Amount (in Rs.)	900000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102a) :-Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	45.114	Cum

2	<p>miscellaneous(ARM28 7) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	1153.6	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	34.608	1 Cum
3	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</p> <p>Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	14.214	Cum
i)	BRM340 : Cement	3.23	45.91122	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	6.3963	1 Cum

iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	12.7926	1 Cum.
4	R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	28.428	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.07590276	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.017454792	1Mtr.
5	Earth Work (AR0115) :-Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	120.098	Cum
i)	BRM029 : Sand for filling and road blinding	1	120.098	1 Cum

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	154.706	1 Cum	40.25	6226.9165
2	BRM028	6.3963	1 Cum	40.25	257.451075
3	BRM056	12.7926	1 Cum.	149.5	1912.4937
Total: 8396.861275					