

ESTIMATION DPR							
State	Odisha	District	Balangir	Block	Patnagarh	Gram Panchayat	Maruan

Work Code	OD/345/3293/115950/420613/00022160 (Imp of Ranibandh at Maruan)
Project Category	Water Body

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Patnagarh	Proposal Date	-
Date of Commencement	27-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Tank	Project Type	Renovation or Rejuvenation
Name of Executant	BISWA PRAKASH CHOUDHARY		

Administrative Approval Details

Approval No.	OD/345/3293/115950/420613/00022160/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/345/3293/115950/420613/00022160/TS
Fund Sanction No.	32
Fund Sanction Amount (in Rs.)	500000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	30.24	Cum
i)	BRM029 : Sand for filling and road blinding	1	30.24	1 Cum

2	<p>Earth Work (AR0102aa) :Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	8.96	Cum
3	<p>Concrete (AR0307) :Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	34.72	Cum
i)	BRM340 : Cement	3.23	112.1456	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	15.624	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	31.248	1 Cum.

4	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	43.68	Cum
i)	BRM340 : Cement	2.29	100.0272	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	20.9664	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	41.9328	1 Cum.
5	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	112	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.29904	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.068768	1Mtr.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	30.24	1 Cum	56.25	1701
2	BRM028	36.5904	1 Cum	56.25	2058.21

3	BRM056	31.248	1 Cum.	185.5	5796.504
4	BRM044	41.9328	1 Cum.	165.5	6939.8784
					Total: 16495.5924