

ESTIMATION DPR							
State	Odisha	District	Deogarh	Block	Reamal	Gram Panchayat	Karlaga

Work Code	OD/351/3347/117207/383139/00024187 (Development Of Rural Haat At Karlaga)
Project Category	Other Infrastructure

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Reamal	Proposal Date	-
Date of Commencement	20-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Development of Rural Haat
Project Sub-Category	Rural Haat	Project Type	New Work
Name of Executant	Deepak Kumar Naik		

Administrative Approval Details

Approval No.	OD/351/3347/117207/383139/00024187/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/351/3347/117207/383139/00024187/TS
Fund Sanction No.	11825
Fund Sanction Amount (in Rs.)	1000000

ROYALTY STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	57.6	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	166.2	Cum
i)	BRM029 : Sand for filling and road blinding	1	166.2	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	39.6	Cum
i)	BRM340 : Cement	2.29	90.684	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	19.008	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	38.016	1 Cum.

4	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	114	Sqm
i)	BRM340 : Cement	0.0358	4.0812	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.71	1 Cum
5	Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	57.6	Cum
i)	BRM340 : Cement	0.672	38.7072	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	16.128	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	20160	1000 Nos

6	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	28.5	Cum
i)	BRM340 : Cement	0.672	19.152	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	7.98	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	9975	1000 Nos
7	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	18	Cum
i)	BRM340 : Cement	3.23	58.14	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	8.1	1 Cum

iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	16.2	1 Cum.
8	Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	96	Sqm
i)	BRM142 : Distemper	0.25	24	1 Kg.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	166.2	1 Cum	40.25	6689.55
2	BRM028	52.926	1 Cum	560.25	29651.7915
3	BRM044	38.016	1 Cum.	401.5	15263.424
4	BRM056	16.2	1 Cum.	401.5	6504.3

Total: 58109.0655