

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Sambalpur	<b>Block</b>	Rengali	<b>Gram Panchayat</b>	Tabadabahal

<b>Work Code</b>	OD/371/3566/121423/381721/00026739 (Imp. of Road with CC/ Gr-II Metalling from Kudamunda Kata to School)
<b>Project Category</b>	Road

<b>Financial Year</b>	2024-25	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Rengali	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	05-08-2025	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance and improvement of Road infrastructure
<b>Project Sub-Category</b>	Mettalling Road	<b>Project Type</b>	Upgradation or Improvement
<b>Name of Executant</b>	Subhalaxmi Behera		

### Administrative Approval Details

<b>Approval No.</b>	OD/371/3566/121423/381721/00026739/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/371/3566/121423/381721/00026739/TS
<b>Fund Sanction No.</b>	1130
<b>Fund Sanction Amount (in Rs.)</b>	784512

### ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Road Work (AR1307)</b> ∴ <b>Supplying &amp; spreading moorum and consolidation with HRR</b> - Supplying & spreading moorum and consolidation with HRR including cost, conveyance, royalty, taxes cost of all labour & material, hire charges of T & P materials required for work as per specification and complete as per direction of Engineer-in-Charge.	-	<b>195.952256</b>	Cum
i)	<b>BRM025</b> : Gravel or moorum	1.28	250.81888768	1 Cum

2	<b>Road Work (AR1341a)</b> <b>:.Providing, laying, spreading and compacting Grading-I stone aggregates of specific sizes using moorum or gravel to water bound macadam -</b> Providing, laying, spreading and compacting Grading-I stone aggregates of specific sizes using moorum or gravel to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per Clause 404 of MoRT&H Specifications for Road & Bridge works(Last Revision).	-	112.134528	Cum
i)	<b>BRM025</b> : Gravel or moorum	0.3	33.6403584	1 Cum
ii)	<b>BRM075</b> : I.R.C. Grade I (90mm-45 mm.)	1.21	135.68277888	1 Cum.

3	<b>Road Work (AR1308)</b> :.moorum and sand admixture laying in sub-base in layers not exceeding 100mm watering and compacting to the required density in O.M.C with PRR - Supplying & spreading moorum and sand admixture in a ratio (70:30) laying in sub-base in layers not exceeding 100mm watering and compacting to the required density in O.M.C with PRR including cost, conveyance, royalty, taxes cost of all labour & material, hire charges of T & P materials required for work as per specification and complete as per direction of Engineer-in-Charge.	-	<b>333.005568</b>	Cum
i)	<b>BRM025</b> : Gravel or moorum	0.89578798586572	298.30238704079	1 Cum
ii)	<b>BRM029</b> : Sand for filling and road blinding	0.384	127.874138112	1 Cum

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM025</b>	582.76163312079	1 Cum	40.25	23456.155733112
2	<b>BRM075</b>	135.68277888	1 Cum.	149.5	20284.57544256
3	<b>BRM029</b>	127.874138112	1 Cum	40.25	5146.934059008
<b>Total: 48887.66523468</b>					