

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Ganjam	<b>Block</b>	Chikiti	<b>Gram Panchayat</b>	Chandapur

<b>Work Code</b>	OD/354/3370/117690/412982/00038797 (Completion of Incomplete Dhoba Samaja Community Hall Baidyanalasan)						
<b>Project Category</b>	Building						

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Chikiti	<b>Proposal Date</b>	21-05-2025
<b>Date of Commencement</b>	01-12-2025	<b>Date of Completion</b>	-
<b>Scheme Name</b>	SFC Devolution of Fund	<b>Scheme Component Name</b>	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
<b>Project Sub-Category</b>	Community Centre	<b>Project Type</b>	Upgradation or Improvement
<b>Name of Executant</b>	SUCHISMITA MISHRA		

### Administrative Approval Details

<b>Approval No.</b>	OD/354/3370/117690/412982/00038797/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/354/3370/117690/412982/00038797/TS
<b>Fund Sanction No.</b>	6911
<b>Fund Sanction Amount (in Rs.)</b>	285722

### ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p><b>R.C.C. Work (AR0404Ac)</b>  <b>:.Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b>  Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder &amp; Bressmer etc)</p>	-	<b>7.799667882</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	27.090586454551	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	3.5098505469	1 Cum
iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.80788043752	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	4.21182065628	1 Cum.
v)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	0.353629142102	1Mtr
vi)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.32391240747158	1Cum.

2	<p><b>Concrete (AR0303a)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	<b>3.490187184</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	7.99252865136	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1.67528984832	1 Cum
iii)	<b>BRM045</b> : Granite Stone broken metal 40mm. size (Hand broken)	0.96	3.35057969664	1 Cum.
3	<p><b>R.C.C. Work (AR0410d) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm</p>	-	<b>16.72254</b>	Sqm
i)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0056666666666667	0.09476106	1Mtr
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.086797945714286	1Cum.

4	<b>R.C.C. Work (AR0410e) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</b>	-	<b>11.77545525</b>	Sqm
i)	<b>BRM094</b> : Non-sal bullahs 125mm. mean dia of any length.	0.0035384615384615	0.0416669955	1Mtr.
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.062349525875	1Cum.
5	<b>R.C.C. Work (AR0410a) :.Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</b>	-	<b>57.0287945493</b>	Sqm
i)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0076666666666667	0.4372207582113	1Mtr
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.28641127929204	1Cum.

6	<b>Plastering (AR1004)</b> :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	<b>66.797257</b>	Sqm
i)	<b>BRM340</b> : Cement	0.0358	2.3913418006	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	1.001958855	1 Cum
7	<b>R.C.C. Work (AR0409)</b> :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	<b>8</b>	Qntl
i)	<b>BRM341</b> : Steel	1.05	8.4	1 Qntl.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM028</b>	6.18709925022	1 Cum	496.25	3070.3480029217
2	<b>BRM060</b>	2.80788043752	1 Cum.	304.5	854.99959322484
3	<b>BRM052</b>	4.21182065628	1 Cum.	304.5	1282.4993898373
4	<b>BRM045</b>	3.35057969664	1 Cum.	304.5	1020.2515176269
<b>Total: 6228.0985036107</b>					