

ESTIMATION DPR							
State	Odisha	District	Jagatsinghpur	Block	Tirtol	Gram Panchayat	Tulanga

Work Code	OD/355/3393/118234/397779/00040193 (REPAIRING OF CC ROAD FROM TAMAPADA BASANTA SWAIN HOUSE TO SAHANI THAKURANI TEMPLE, VILLAGE TAMAPADA.)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Tirtol	Proposal Date	07-12-2024
Date of Commencement	18-10-2025	Date of Completion	02-12-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant	MONALISA MALLICK		

Administrative Approval Details

Approval No.	OD/355/3393/118234/397779/00040193/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/355/3393/118234/397779/00040193/TS
Fund Sanction No.	30636
Fund Sanction Amount (in Rs.)	143788

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<p>Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	1.344	Cum

i)	BRM340 : Cement	2.29	3.07776	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	0.64512	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1.29024	1 Cum.
2	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	14.87808	Cum
i)	BRM340 : Cement	3.23	48.0561984	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	6.695136	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	13.390272	1 Cum.

3	R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	6.72	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0179424	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.00412608	1Mtr.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM028	7.340256	1 Cum	199.25	1462.546008
2	BRM045	1.29024	1 Cum.	444.5	573.51168
3	BRM056	13.390272	1 Cum.	444.5	5951.975904
Total: 7988.033592					