

ESTIMATION DPR							
State	Odisha	District	Nayagarh	Block	Dasapalla	Gram Panchayat	Tumandi

Work Code	OD/367/3524/120625/405488/00040355 (Imp. of road from Narajipada to Karadakancha Nala)
Project Category	Road

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Dasapalla	Proposal Date	-
Date of Commencement	30-07-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	Upgradation or Improvement
Name of Executant	Rasmi Ranjan Dash		

Administrative Approval Details

Approval No.	OD/367/3524/120625/405488/00040355/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/367/3524/120625/405488/00040355/TS
Fund Sanction No.	9114
Fund Sanction Amount (in Rs.)	310000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	22.265	Cum
i)	BRM029 : Sand for filling and road blinding	1	22.265	1 Cum

2	<p>Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	22.265	Cum
i)	BRM340 : Cement	2.29	50.98685	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	10.6872	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	21.3744	1 Cum.
3	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	22.1874375	Cum
i)	BRM340 : Cement	3.23	71.665423125	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	9.984346875	1 Cum

iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	19.96869375	1 Cum.
4	R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	24.4	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.065148	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.0149816	1Mtr.

5	<p>Earth Work (AR0102b) :.Earth work in hard soil or gravelly soil in embankment, roads etc. within 50m initial lead and 1.5m initial lift and Compaction with P.R.R - Earth work in hard soil or gravelly soil in embankment, roads etc. within 50m initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per specification approved by the Department alongwith proper compaction with P.R.R. including hire and running charges of P.R.R. (section measurement to be taken on the finished compacted section of the fill) as per direction of Engineer-in-Charge.</p>	-	36.9	Cum
---	--	---	------	-----

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	22.265	1 Cum	305.25	6796.39125
2	BRM028	20.671546875	1 Cum	305.25	6309.9896835938
3	BRM045	21.3744	1 Cum.	199.5	4264.1928
4	BRM056	19.96869375	1 Cum.	199.5	3983.754403125
Total: 21354.328136719					