

ESTIMATION DPR							
State	Odisha	District	Dhenkanal	Block	Bhuban	Gram Panchayat	Ektali

Work Code	OD/352/3349/117245/402582/00041686 (REPAIR AND MAINTENANCE OF CC ROAD FROM RD ROAD TO CHANDAR)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Bhuban	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	OD/352/3349/117245/402582/00041686/TS
Fund Sanction No.	32004
Fund Sanction Amount (in Rs.)	270000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	32.508	Cum

i)	BRM340 : Cement	3.23	105.00084	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	14.6286	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	29.2572	1 Cum.
2	R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	17.2	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.045924	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.0105608	1Mtr.
3	Earth Work (AR0115) :Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	36.12	Cum
i)	BRM029 : Sand for filling and road blinding	1	36.12	1 Cum

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM028	14.6286	1 Cum	311.25	4553.15175

2	BRM056	29.2572	1 Cum.	305.5	8938.0746
3	BRM029	36.12	1 Cum	311.25	11242.35
					Total: 24733.57635