

ESTIMATION DPR							
State	Odisha	District	Koraput	Block	Kotpad	Gram Panchayat	Chandili

Work Code	OD/363/3472/119815/428124/00043057 (repair and maintenance of AWC birahandi)
Project Category	Building

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Kotpad	Proposal Date	-
Date of Commencement	29-07-2025	Date of Completion	-
Scheme Name	Asset Management Women and Child Development Department	Scheme Component Name	Self/Personal Deposit
Project Sub-Category	AWC	Project Type	Repair and Maintenance
Name of Executant	Rajesh Kumar Dhir		

Administrative Approval Details

Approval No.	OD/363/3472/119815/428124/00043057/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/363/3472/119815/428124/00043057/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	45000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Plastering (AR1033) :.White washing two coats with stone lime in any surface - White washing two coats with stone lime in any surface including all costs of labour, coaltar and brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	228.69	Sqm

2	Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	228.69	Sqm
i)	BRM142 : Distemper	0.25	57.1725	1 Kg.
3	Painting(AR0903i) :.Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	17.28	Sqm
i)	BRM141 : Enamel paint	0.125	2.16	1 Litre

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
					Total: 0