

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Koraput	<b>Block</b>	Laxmipur	<b>Gram Panchayat</b>	Bhitaragada

<b>Work Code</b>	OD/363/3475/119855/428864/00043066 (IMPROVEMENT OF ROAD AT GONEIPADAR VILLAGE TO SCHOOL)
<b>Project Category</b>	Road

<b>Financial Year</b>	2024-25	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Laxmipur	<b>Proposal Date</b>	16-07-2024
<b>Date of Commencement</b>	29-07-2025	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	All Weather Connectivity
<b>Project Sub-Category</b>	Pavor Block	<b>Project Type</b>	Upgradation or Improvement
<b>Name of Executant</b>	RANJIT KHOSLA		

### Administrative Approval Details

<b>Approval No.</b>	OD/363/3475/119855/428864/00043066/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/363/3475/119855/428864/00043066/TS
<b>Fund Sanction No.</b>	1440
<b>Fund Sanction Amount (in Rs.)</b>	300000

### ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0115)</b> :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	31.683	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	31.683	1 Cum

2	<p><b>Concrete (AR0304)</b>  <b>:.Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal -</b>  Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	6.256	Cum
i)	<p><b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)</p>	0.96	6.00576	1 Cum.
ii)	<p><b>BRM340</b> : Cement</p>	1.72	10.76032	1 Qntl.
iii)	<p><b>BRM028</b> : Screened and washed sharp sand for mortar</p>	0.48	3.00288	1 Cum
3	<p><b>miscellaneous(ARM287)</b> <b>:.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</b>  Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	316.83	Sqm
i)	<p><b>BRM029</b> : Sand for filling and road blinding</p>	0.03	9.5049	1 Cum

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	41.1879	1 Cum	87.4	3599.82246
2	BRM044	6.00576	1 Cum.	149.5	897.86112
3	BRM028	3.00288	1 Cum	308.2	925.487616
					<b>Total: 5423.171196</b>