

ESTIMATION DPR							
State	Odisha	District	Nuapada	Block	Komna	Gram Panchayat	Darlipada

Work Code	OD/368/3533/120802/421839/00052111 (IMP OF ROAD FROM JAMBAHALI BASTI TO PRIMARY SCHOOL JAMBAHAL OF DARLIPADA GP 5THSFC)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Komna	Proposal Date	-
Date of Commencement	12-12-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	Upgradation or Improvement
Name of Executant	Bijaya Kumar Nayak		

Administrative Approval Details

Approval No.	OD/368/3533/120802/421839/00052111/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/368/3533/120802/421839/00052111/TS
Fund Sanction No.	14036
Fund Sanction Amount (in Rs.)	400000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	49.5225	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	25.915	Cum
i)	BRM029 : Sand for filling and road blinding	1	25.915	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	34.435	Cum
i)	BRM340 : Cement	2.29	78.85615	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	16.5288	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	33.0576	1 Cum.

4	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	42.6	Sqm
i)	<p>BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)</p>	0.00267	0.113742	1Cum.
ii)	<p>BRM092 : Non-sal bullahs 75mm. mean dia of any length.</p>	0.000614	0.0261564	1Mtr.
5	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	25.915	Cum
i)	<p>BRM340 : Cement</p>	3.23	83.70545	1 Qntl.
ii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.45	11.66175	1 Cum
iii)	<p>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</p>	0.9	23.3235	1 Cum.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	25.915	1 Cum	71.25	1846.44375
2	BRM028	28.19055	1 Cum	71.25	2008.5766875
3	BRM044	33.0576	1 Cum.	175.5	5801.6088
4	BRM056	23.3235	1 Cum.	175.5	4093.27425
					Total: 13749.9034875