

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Jagatsinghpur	<b>Block</b>	Erasama	<b>Gram Panchayat</b>	Nuadihi

<b>Work Code</b>	OD/355/3388/118109/397331/00062267 (Repair and maintenance of PHC building at Mallipur)
<b>Project Category</b>	Building

<b>Financial Year</b>	2023-24	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Erasama	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	20-11-2025	<b>Date of Completion</b>	-
<b>Scheme Name</b>	Asset Management Health and Family Welfare Department	<b>Scheme Component Name</b>	Self/Personal Deposit
<b>Project Sub-Category</b>	Primary Health Centre	<b>Project Type</b>	Repair and Maintenance
<b>Name of Executant</b>	Susanta Kumar Nanda		

### Administrative Approval Details

<b>Approval No.</b>	OD/355/3388/118109/397331/00062267/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/355/3388/118109/397331/00062267/TS
<b>Fund Sanction No.</b>	
<b>Fund Sanction Amount (in Rs.)</b>	155000

### ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Painting(AR0903b)</b> :.Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	<b>39.762484</b>	Sqm
i)	<b>BRM137</b> : Red oxide Primer	0.054	2.147174136	1 Litre
ii)	<b>BRM141</b> : Enamel paint	0.125	4.9703105	1 Litre

2	<p><b>Other Building Items. (AR1902) :.cement based wall putty (water based) -</b>  Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&amp;P,etc.complete. and as per the direction of Engineer in Charge.</p>	-	147.71577	Sqm
3	<p><b>Painting(AR0918cb) :.Finishing wall two coats with weather coat with one coat waterbound Primer -</b>  Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)</p>	-	196.211136	Sqm
i)	<b>BRM255</b> : Weather Coat (I.S.I.)	0.125	24.526392	1 Ltr
ii)	<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	17.722296154839	1 Ltr
4	<p><b>Painting(AR0921b) :.Finishing wall One Coat with distemper of approved shades with one coat water bound Primer on old work (Inside) -</b>  Finishing wall surface with One Coat with distemper of approved shades above one coat waterbound Primer on old work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge..(Inside)</p>	-	319.679223	Sqm
i)	<b>BRM142</b> : Distemper	0.166	53.066751018	1 Kg.

ii)	<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.084	26.853054732	1 Ltr
-----	---	-------	--------------	-------

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
					<b>Total: 0</b>