

ESTIMATION DPR

State	Odisha	District	Ganjam	Block	Buguda	Gram Panchayat	Arakhapur
--------------	--------	-----------------	--------	--------------	--------	-----------------------	-----------

Work Code	OD/354/3368/117654/410446/00062811 (Maintenance & Improvement of CC Road from GP Office to Malatipathapur)
Project Category	Road

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Buguda	Proposal Date	-
Date of Commencement	06-11-2025	Date of Completion	18-11-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant	Prasan Kumar Sahu		

Administrative Approval Details

Approval No.	OD/354/3368/117654/410446/00062811/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3368/117654/410446/00062811/TS
Fund Sanction No.	12614
Fund Sanction Amount (in Rs.)	147984

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
---------------	-------------------------------	--	----------------------------------	-------------

1	<p>Earth Work (AR0122Ai16) :.Earthwork in all kinds of soil within 50m lead, with four extra lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth - Earthwork in all kinds of soil within 50m lead, with four extra lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.</p>	-	4.8668	Cum
2	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	16.79	Cum
i)	<p>BRM029 : Sand for filling and road blinding</p>	1	16.79	1 Cum
3	<p>Concrete (AR0304) :.Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal - Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	4.8668	Cum

i)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	4.672128	1 Cum.
ii)	BRM340 : Cement	1.72	8.370896	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.48	2.336064	1 Cum
4	miscellaneous(ARM28 7) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	150.75	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	4.5225	1 Cum
5	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	55.2	Sqm

i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.147384	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.0338928	1Mtr.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	21.3125	1 Cum	205.25	4374.390625
2	BRM044	4.672128	1 Cum.	254.5	1189.056576
3	BRM028	2.336064	1 Cum	205.25	479.477136
Total: 6042.924337					