

ESTIMATION DPR							
State	Odisha	District	Kendujhar	Block	Ghasipura	Gram Panchayat	Sainkul

Work Code	OD/361/3446/119327/387299/00075106 (CONST OF BOTH SIDE DRAIN FROM PWD ROAD TO SANKARPUR)
Project Category	CD Work

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Ghasipura	Proposal Date	-
Date of Commencement	27-01-2026	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
Project Sub-Category	Drain Masonry or Cement Concrete	Project Type	New Work
Name of Executant	Shradhanjali Sahoo		

Administrative Approval Details

Approval No.	OD/361/3446/119327/387299/00075106/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/361/3446/119327/387299/00075106/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	200000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	28.98	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.245	Cum
i)	BRM029 : Sand for filling and road blinding	1	7.245	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	19.845	Cum
i)	BRM340 : Cement	2.29	45.44505	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	9.5256	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	19.0512	1 Cum.

4	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	100.8	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.269136	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.0618912	1Mtr.
5	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	1.995	Cum
i)	BRM340 : Cement	3.23	6.44385	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.89775	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1.7955	1 Cum.

6	Plastering (AR1027) :6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	140.7	Sqm
i)	BRM340 : Cement	0.0372	5.23404	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	1.05525	1 Cum

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	7.245	1 Cum	190.25	1378.36125
2	BRM028	11.4786	1 Cum	190.25	2183.80365
3	BRM044	19.0512	1 Cum.	294.5	5610.5784
4	BRM056	1.7955	1 Cum.	294.5	528.77475
Total: 9701.51805					