

Estimate Abstract

OD/350/3336/116944/399133/00085920 : PPMS17-03-2000

Block : Baranga, Gram Panchayat : Munduli

Created By:DEBASMITA LENKA

SI No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0103a1 (Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m to 75m lead and 1.5m) : Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per specification approved by the dept.			
	88.49	Cubic Meter	326.913972	28928.61738228
2	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.698	Cubic Meter	5790.0926803	102473.06025595
Total Amount (A) : 131401.67763823				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ Rs.1000	-	1000
2	Display Citizen Board @ Rs.1000	-	1000
Additional Components Amount (F) : 2000			

Grand Total Amount (A + F) : 133401.67763823

DEBASMITA LENKA
JE
Baranga Block

Aditya Narayan Mishra
AEE
Baranga Block

Swagat Das
BDO
Baranga Block