

**Estimate Abstract**

**OD/356/3400/118416/400977/00085989 : Priya road Construction  
Block : Jajpur, Gram Panchayat : Badasuar  
Created By:Pratap Kumar Sethy**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Road Work : AR1332a (Laying 20mm thick premix carpet) :</b> Laying 20mm thick premix carpet using 0.23cum of 13.2mm to 5.6mm size crushed stone chipping and 12.70kg. viscosity grade (VG-30) of bitumen (from Paradip) for 9.29sqm including cost conveyance, royalty, taxes, cess etc. of all materials, hire and running charges of PRR etc. complete as per specification and direction of the Engineer-in-Charge.			
	17.837376	Square Meter	160.39328581416	2860.9953469426
2	<b>Road Work : AR1321aii (Laying 20mm thick premix carpet using 0.27cum of 13.2mm to 5.6mm (VG-30) bitumen (from Kakinada)) :</b> Laying 20mm thick premix carpet using 0.27cum of 13.2mm to 5.6mm size crushed stone chipping and 14.60kg. viscosity grade (VG-30) bitumen (from Kakinada) for 10sqm including hand packing to proper camber and consolidation with PRR including cost conveyance, royalty, taxes, cess etc. of all materials, hire and running charges of PRR, hot mix plant, bitumen boilers and all other T & P articles required for the work complete as per specification and direction of the Engineer-in-Charge.			
	22.29672	Square Meter	176.85009105667	3943.1769622651
3	<b>Road Work : AR1322ai (Laying 6mm thick precoated seal coat Type-B (VG-30) bitumen (from Haldia)) :</b> Laying 6mm thick precoated seal coat Type-B using 0.06 cum of 6.7mm size chips as per sieve analysis and 6.8Kg of viscosity grade (VG-30) bitumen (from Haldia) per 10sqm.including cost conveyance, royalty, taxes, cess etc. of all materials, hire and running charges of PRR, hot mix plant, tar boiler and all other T&P articles etc. required for the work complete as per specification and direction of the Engineer-in-Charge.			
	576	Square Meter	75.031183961944	43217.96196208
				<b>Total Amount (A) : 50022.134271287</b>

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for PH Work @ Rs.1	-	1
2	Provision for EI Work @ Rs.1	-	1
3	Provision for Contingency @ 10%	-	5002.2134271287
4	Display Citizen Board @ Rs.2	-	2
5	Any Other Lumpsum @ Rs.2	-	2
6	Provision for survey investigation and quality control @ 5%	-	2501.1067135644

**Additional Components Amount (F) : 7509.3201406931**

**Grand Total Amount (A + F) : 57531.454411981**

**Pratap Kumar Sethy  
JE  
Jajpur Block**

**SAROJ KUMAR SWAIN  
AEE  
Jajpur Block**

**Hemanta Kumar Mohanta  
BDO  
Jajpur Block**