

Analysis

OD/350/3336/116944/399133/00085920 : PPMS17-03-2000

Block : Baranga, Gram Panchayat : Munduli

Created By:Swagat Das

Item 1
Earth Work (AR0103a1): Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per specification approved by the dept.
Sub-Item of Work Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m to 75m lead and 1.5m

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Earth Work (AR0103a)					
LR002 : Female mulia	33.53	Per day	462	15490.86	0
LR001 : Male mulia	33.53	Per day	462	15490.86	0
Combine :: Earth Work (AR0107)					
LR001 : Male mulia	3	Per day	462	1386	0
Total Amount (a+b+c)				32367.72	
Total GST (a)					0
LABOUR CESS @ 1% (+)					323.6772
Grand Total					32691.3972
Say For Unit 1 (Grand Total/100)					326.913972

Item 2
Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	850	1946.5	350.37

BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	88.88	42.6624	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	759.6	729.216	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	276.01	132.4848	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	276.01	264.9696	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	140.25	67.32	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	249.5	239.52	0

Total Amount (a+b+c)	5382.39503
Total GST (a)	350.37
LABOUR CESS @ 1% (+)	57.3276503
Grand Total	5790.0926803
Say For Unit 1 (Grand Total/1)	5790.0926803

DEBASMITA LENKA
JE
Baranga Block

Aditya Narayan Mishra
AEE
Baranga Block

Swagat Das
BDO
Baranga Block