

Analysis

OD/366/3520/275428/427196/00085941 : SR Community Hall
Block : Raighar, Gram Panchayat : Hatigam
Created By:CPPPMS

Item 1
Other Building Items. (AR1902): Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.
Sub-Item of Work Third Floor

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0038 : Cement based putty	8	kg	30	240	0
LR001 : Male mulia	0.62285439	Per day	462	287.75872818	0
LR025 : Mason	0.5463635	Per day	562	307.056287	0
Total Amount (a+b+c)				834.81501518	
Total GST (a)					0
LABOUR CESS @ 1% (+)				8.3481501518	
Grand Total				843.1631653318	
Say For Unit 1 (Grand Total/10)				84.31631653318	

Item 2
Other Building Items. (AR1902): Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.
Sub-Item of Work cement based wall putty (water based)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0038 : Cement based putty	8	kg	30	240	0
LR001 : Male mulia	0.57	Per day	462	263.34	0
LR025 : Mason	0.5	Per day	562	281	0
Total Amount (a+b+c)				784.34	
Total GST (a)					0
LABOUR CESS @ 1% (+)				7.8434	
Grand Total				792.1834	

Say For Unit 1 (Grand Total/10)	79.21834
---------------------------------	----------

Item 3

Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work
Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2017.18	153.30568	0
BRM340 : Cement	1.074	1 Qntl.	561	602.514	108.45252
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	76.13	15.9873	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	24.787	1.883812	0
BRM340 : Cement	1.074	1 Qntl.	25.976	27.898224	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	367.15	77.1015	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	10.5829445	105.829445	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	40.25	8.4525	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)	9823.612461
Total GST (a)	108.45252
LABOUR CESS @ 1% (+)	99.32064981
Grand Total	10031.38563081
Say For Unit 1 (Grand Total/10)	1003.138563081

TANMAY PATTNAIK
JE
Raighar Block

SIDDHARTH SHANKAR RANA
AEE
Raighar Block

RITU SINGH
BDO
Raighar Block