

Detailed Estimate

OD/366/3520/120531/427237/00085972 : Kharitbipal

Block : Raighar, Gram Panchayat : Bobei

Created By: DURGAPRASAD HANSDAH

1. Road Work (AR1341c) : Providing, laying, spreading and compacting Grading-II stone aggregates of specific sizes using moorum or gravel to water bound macadam								
Providing, laying, spreading and compacting Grading-II stone aggregates of specific sizes using moorum or gravel to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per Clause 404 of MoRT&H Specifications for Road & Bridge works(Last Revision).								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	1	1.000	1.000	1.000	1.000	1.000	1.000	-
Total Quantity					1 cum (cum)		1 Cum (Cubic Meter)	
Amount					1 X 1699.3936670944		1699.39	

Total Amount (A) : 1699.39

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for PH Work @ Rs.1	-	1
2	Provision for EI Work @ Rs.1	-	1
3	Provision for Contingency @ Rs.1	-	1
4	Display Citizen Board @ Rs.1	-	1
5	Any Other Lumpsum @ Rs.2	Ok	2
6	Provision for survey investigation and quality control @ Rs.1	-	1
Additional Components Amount (F) :			7

Grand Total Amount (A + F) : 1706.3936670944

DURGAPRASAD HANSDAH
JE
Raighar Block

SIDDHARTH SHANKAR RANA
AEE
Raighar Block

RITU SINGH
BDO
Raighar Block